

**SURVEY & REMONUMENTATION**

JUN 06 1995

**COMMISSION**  
For corners in

**LAND CORNER RECORDATION CERTIFICATE** LIBER 4 PAGE 113  
Filing Requirement of Act 74, Mich. P.A. 1970

<u>ST. JOSEPH</u> (County)	Located In:	Corner Code #
LEONIDAS TOWNSHIP	T 55 R 9W	I-3
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

STATE OF MICHIGAN  
ST. JOSEPH COUNTY  
FILED

4 APR 95 9:49 A.M.

CYNTHIA JARRATT  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2							
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, DAVID W. MOSTROM, in a field survey on JANUARY 13, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

(I-3) CORNER COMMON TO SECTION 2, 3 10, 11

GLO - 10" BEECH N53°E 0.13  
7" BEECH N67°W 0.15

1890 SURVEY IN BOOK A, PG. 632

STONE SET BY FORMER SURVEYOR  
12" BLK. WALNUT = N46°W 68 LINKS

1878 SURVEY IN BOOK A, PG. 278

STONE SET FROM ORIG. BRG'S  
NO WITNESSES

1970 ROAD COMMISSION

CORNER RE-ESTABLISHED BY USING  
CORNERS  $\frac{1}{4}$  &  $\frac{1}{2}$  MILE EAST,  
SOUTH & WEST

1975 CORNER RECORDS  
BOOK 2, PG. 296 &  
BOOK 3, PG. 182

BOX AND PIPE  
COR. POST N43°W 47.35'  
20" SYCAMORE = S41° 50.9'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(I-3)

FOUND 3/4" X 36" PIPE IN MON. BOX IN C/L - C/L OF ROADS  
CORNER FALLS IN CUT AREA OF ROADWAY  
CORNER POST = N43°W 47.35' (FACE)  
30" SYCAMORE = S41°W 52.50'

RATIFIED BY PEER GROUP  
IN ACCORDANCE WITH P.A. 345  
ON March 13, 1995  
Wm CO. REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(I-3) CORNER COMMON TO SECTIONS 2, 3, 10, 11

SET 5/8" X 24" IRON BAR W/STD. CAP IN MON. BOX

IRON ANCHOR POST = N43°W 47.60'

SW HOUSE CORNER = S35°E 109.80'

PK NAIL & WASHER 2' HIGH IN NW SIDE OF 30" SYCAMORE = S41°W 52.50'

PK NAIL & WASHER 4' HIGH IN N. SIDE OF 12" MAPLE = S70°W 106.66'



Signed by J. W. Mostrom

Date MARCH 23, 1995

Surveyor's Michigan License No. 32339

**REMONUMENTATION**