

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY <u>18</u> T. <u>5</u> S., R. <u>10</u> W.		A-5, C-5
2. PROPERTY CONTROLLING IN SECTION _____, T. _____ S., R. _____ E. W.		
3. MISCELLANEOUS PROPERTY IN SECTION _____, T. _____ S., R. _____ E. W.		
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

St. Joseph Co

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Donald L. Bissell, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on June, 1983, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

<p>A-5 Mon. Box in Pav't. with 3/8" Iron Pipe</p>	<p>C-5 Found: Pointed stone with witnesses West 17.15' p.k. nail in anchor post North 26.55' p.k. nail in anchor post S 29°W. 12.15' p.k. nail in 8" hedge N 76°W. 12.70' p.k. nail in 12" hedge N 34°E. 23.70' p.k. nail in 12" hedge Set: 4" x 36" concrete monument.</p>
---	---

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

<p>A-5 Mon. box with 3/8 iron pipe S 85°E., 40.75', 36" Oak S 52°E., 36.41', Power pole S 22°E., 72.43', Butternut N 60°W., 66.63', Anchor pole</p>	<p>C-5 4" x 36" Concrete mon. with alum. cap West 17.15' P.k. nail in anchor post North 26.55' p.k. nail in anchor post S 29°W, 12.15' p.k. nail in 8" hedge N 76°W, 12.20' p.k. nail in 12" hedge N 34°E, 23.70' p.k. nail in 12" hedge.</p>
---	--

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Donald L. Bissell CHIEF OF SURVEY PARTY DATE 7-12-83
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. 18655