

MAY 05 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 LIBER 4 PAGE 123

For corners in

ST. JOSEPH (County) Located In: Corner Code #7
MENDON TWP.
1. Public Land Survey T 5S R 10W A-8
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R

STATE OF MICHIGAN
ST. JOSEPH COUNTY
FILED
12 APR 95 3:15 P.M.
CYNTHIA JARRATT
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat
5. Private Claims

Grid table with columns A-M and rows 2-13 containing numbers 1-36.

I, WAYNE A. MOSTROM, in a field survey on APRIL 9, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

A-8
1974 L.C.R.C. IN 3/007 1992 SURVEY BY STEPENSON
IRON BAR SET FOUND 1/2" BAR CAPPED #7874
10" HARDWOOD = S48°E 18.6' P.P. = N20°E 33.8'
R.R. TIE = N40°W 36.9' "T" RAIL = NORTH 27.3'
P.P. = S80°W 82.5'
1974 SURVEY BY MOSTROM
SHOWS ABOVE PLUS: P.P. = N6°40'E 25.1'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-8
FOUND 1/2" X 18" IRON BAR CAPPED #7874 9' SOUTH OF CL GRAVEL RDWY
PARK TWP. COR. (IRON OVER STONE) = NORTH 16.17' (MEAN OF GLO JOGS)
P.P. = N20°E 33.8'
"T" RAIL = NORTH 27.3'
P.P. = S80°W 82.5'

RATIFIED BY PEER GROUP
IN ACCORDANCE WITH P.A. 345
ON April 10, 1995
CO. REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-8 SET 5/8" X 10" BAR W/TH STD. CAP IN CONC. OVER STONE IN MON. BOX
PARK COR. (STD. COUNTY MON.) = NORTH 16.17'
N & W IN E. SIDE POWER POLE = N20°E 33.80' (C.P. CO. POLE #4-45)
N. EDGE R.R. RAIL = NORTH 27.3'
N & W IN NORTH SIDE OF POWER POLE = S80°W 82.50'
N & W IN W. SIDE OLD POLE = SOUTH 84.11'
COR. IS ON FENCE LINE TO THE NORTH PROJECTED.



Signed by [Signature] Date 4/12/95
Surveyor's Michigan License No. 14100

LIBER 4 PAGE 123