

SURVEY & REMONUMENTATION COMMISSION
 APR 10 1995

004 PG 043

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

FILED

JUN 27 12 47 PM '94

Cynthia A. Bennett
 REGISTER OF DEEDS
 ST. JOSEPH COUNTY

For corner in _____
 ST. JOSEPH (County)

Located In: _____ Corner Code: # _____

1. Public Land Survey T 5S R 10W C-8
 T _____ R _____
 T _____ R _____
 T _____ R _____

2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19	20			21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, WAYNE A. MOSTROM, in a field survey on MAY 13, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

C-8
1888 SURVEY OF O.H. TODD L.C.R.C. IN 1974 (3/07)
 1/4 COR WAS SET BY FORMER SURVEYOR (WRONG CORNER WAS REFERENCED)
1907 SURVEY BY MCCOY 1979 SURVEY BY MOSTROM
 STONE BY FORMER SURVEYOR FOUND 3/4" SHEARED PIPE IN MON. BOX
 P.P. = N43°W 43°W 41.59', BRACE POLE = S14°W 31.73'
 IRON ROAD SIGN = S14°E 28.75'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-8
 FOUND SHEARED PIPE OVER STONE 16" DEEP IN MON. BOX
 P.P. = N43°W 41.59'
 BRACE POLE = S14°W 31.73'
 IRON ROAD SIGN = S14°E 28.75'

RATIFIED BY PEER GROUP
 IN ACCORDANCE WITH P.A. 345
 ON JUNE 13, 1994
Wm CO. REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-8 1/4 CORNER BETWEEN SEC'S 19 & 20
 SET 5/8" X 14" IRON BAR WITH STD. CAP OVER STONE IN MON. BOX
 N & W IN NW SIDE P.P. = S18°W 31.71'
 N & W IN NE SIDE P.P. = N38°W 41.59'
 CENTER OF 3" PINE = S66°W 88.75'
 CENTER OF 7" PINE = S50°W 61.85'
 COR. IS 1.3' S. OF PAVED RDWY & 2' OF CL GRAVEL RDWY. TO N.



Signed by *Wayne A. Mostrom*
 Surveyor's Michigan License No. 14100

Date 6/15/94

REMONUMENTATION