

MAY 05 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 4 PAGE 120

For corners in

ST. JOSEPH (County)

Located In:

Corner Code #

MENDON TWP.

1. Public Land Survey

T 5S R 10W

E-9

2. Property Controlling in Section

S T R

3. Miscellaneous

S T R

Property in Sec.

S T R

4. Lot No. , Recorded Plat

5. Private Claims

STATE OF MICHIGAN ST. JOSEPH COUNTY FILED

11 APR 95 2:13 P.M.

CYNTHIA JARRATT REGISTER OF DEEDS

Register of Deeds Stamp & File Number

Grid table with columns A-M and rows 2-13. A dot is marked at row 9, column D.

WAYNE A. MOSTROM in a field survey on APRIL 8, 1995 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

E-9

L.C.R.C. IN L-3, P-09 & 1974 SURVEY

GLO = SET POST

20" W.O. = N37°E 40 LKS.

18" W.O. = S16 1/2°W 117 LKS

FD. POINTED STONE EMBEDDED IN CONC.

RR RAIL = NORTH 0.38'

PK IN TREE = SOUTH 1.21'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-9

FD. POINTED STONE W/NOTCH ON TOP IN CONC. BASE COR. IS IN LINE WITH OLD FENCE TO WEST

RATIFIED BY PEER GROUP IN ACCORDANCE WITH P.A. 348 ON April 10, 1995 CO. REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-9 NOTCHED STONE IN CONC. BASE 7" ABOVE GRADE

NO IRON WAS SET DUE TO MAGNATUDE OF PHYSICAL EVIDENCE FOUND

N & W ON N. SIDE 8" LOCUST CLUSTER = S88°W 16.15'

N & W ON E. SIDE 24" CHERRY = N45°W 39.45'

N & W ON W. SIDE 18" CHERRY = N25°W 24.12'

N & W ON E. SIDE 24" CATALPA = S25°W 26.41'

COR. IS IN LINE WITH OLD FENCE LINE TO WEST



Signed by [Signature]

Date 4/11/95

Surveyor's Michigan License No. 14100

LIBER 4 PAGE 120