

MAY 07 1997

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 4 PAGE 289

For corners in St. Joseph Located In: _____ Corner Code # _____
(County)

1. Public Land Survey T 5S R 10W G-11
T _____ R _____
T _____ R _____
T _____ R _____

2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

4. Lot No. _____ Recorded Plat _____

5. Private Claims _____

STATE OF MICHIGAN
ST. JOSEPH COUNTY
FILED

30 DEC 96 2:00 P.M.

CYNTHIA JARRATT
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, Donald C. Andrews, in a field survey on May 2, 1996, do hereby certify that under requirements of P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G-11
GLO - Post
W. Mostrom said Sayers found Stone (no witness). Stone North 1333.67 feet of N1/8th corner of East line of Section 33. Also N1/8th is 3968.43 feet North of SE corner of Section 33.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


G-11
Found record stone in E-W fence at the above record distance on the North side of a 38" Oak.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-11
Left stone undisturbed, the standard remon iron would have had to have been driven into the tree. I was not sure whether I could get it driven into the Oak tree. I used the St. Joseph Co. remon witness markers. 1) 38" Oak S80°E 2.08', 2) 8" Ash West 13.50', 3) 18" Cherry N80°W 19.85', 4) 18" twin Hickory S80°W 22.51'

RATIFIED BY PEER GROUP
IN ACCORDANCE WITH P.A. 345
ON May 13, 1996
Wass CO., REPRESENTATIVE

Signed by Donald C. Andrews
Donald C. Andrews, P.S.
Surveyor's Michigan License No. 33967



Date 12/23/96

| | A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|---|----|---|----|---|----|---|----|---|----|---|---|
| 2 | 6 | | 5 | | 4 | | 3 | | 2 | | 1 | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | | 8 | | 9 | | 10 | | 11 | | 12 | | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | | 17 | | 16 | | 15 | | 14 | | 13 | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | | |
| 13 | | | | | | | | | | | | | |

LIBER 4 PAGE 289