

004 PG 040

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

FILED

JUN 27 12 47 PM '94

Cynthia A. Bennett
REGISTER OF DEEDS
ST. JOSEPH COUNTY

For corners in

| | | |
|---------------------------------------|-------------------------|---|
| ST. JOSEPH (County) | Located In: | Corner Code #/ |
| 1. Public Land Survey | T 5S R 10W | I-9 |
| | T _____ R _____ | |
| | T _____ R _____ | |
| | T _____ R _____ | |
| 2. Property Controlling in Section | S _____ T _____ R _____ | SURVEY & REMONUMENTATION |
| | S _____ T _____ R _____ | |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | AUG 31 1994 |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

COMMISSION

WAYNE A. MOSTROM, in a field survey on MAY 13, 1994, to hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

| A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|----|----|----|----|----|---|---|---|---|---|---|
| 2 | 6 | 5 | 4 | 3 | 2 | 1 | | | | | | |
| 3 | | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | |
| 5 | | | | | | | | | | | | |
| 6 | 18 | 17 | 16 | 15 | 14 | 13 | | | | | | |
| 7 | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | |
| 9 | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | |
| 11 | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | |
| 13 | | | | | | | | | | | | |

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1876 SURVEY BY N.S. ANDREWS

ANDREWS PREVIOUSLY SET STONE
IN 1858 FROM OLD BEARINGS
17" Y.O. = S46°E 62 1/2 LKS

1974 L.C.R.C. (3/11) BY SAYERS

PIPE IN MON BOX
21" MAPLE = WEST 32.45'
TOP/FIRE HYD. = SE 49.1'

LCRC IN (1/29)

IRON FOUND IN MON. BOX
21" MAPLE = WEST 32.45'

SAYERS SURVEY IN 1960'S

SHOWS IRON SET 33' WEST

SAYERS 1977 SURVEY

21" MAP = W. 32.45, HYD. = SE 49.1'

3. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-9

FOUND 1" IRON PIPE IN CONC. IN MON. BOX
IRON = WEST 33'
FIRE HYD = SE 49.1'
21" MAPLE = WEST 32.45'

RATIFIED BY PEER GROUP
IN ACCORDANCE WITH P.A. 345
ON JUNE 13, 1994
W.A. Co. REPRESENTATIVE

3. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-9 (CORNER COMMON TO SEC'S 22, 23, 26, 27)

SET 5/8" X 3" BAR W/STD. CAP IN 1" IRON PIPE IN CONC. IN MON. BOX
TOP FIRE HYDRANT = S29°E 49.1'
NW COR OF CONC. BASE OF STONE PILLAR = S63°E 56.12'
N & W IN S. SIDE 32" MAPLE = N88°W 32.45'
N & W IN E. SIDE POLE = S16°W 79.56'

Signed by *Wayne A. Mostrom*

Date 6/15/94

Surveyor's Michigan License No. 14100



REMONUMENTATION