

**SURVEY &  
REMONUMENTATION**

JAN 17 1996

**COMMISSION LAND CORNER RECORDATION CERTIFICATE**

Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 4 PAGE 160

For corners in

<u>ST. JOSEPH</u> (County)	Located In:	Corner Code #
<u>MENDON TWP.</u>		
1. Public Land Survey	T <u>5S</u> R <u>10W</u>	<u>M-4</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

STATE OF MICHIGAN  
ST. JOSEPH COUNTY  
FILED

24 AUG 95 2:31 P.M.

CYNTHIA JARRATT  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, WAYNE A. MOSTROM, in a field survey on SEPTEMBER 13, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

<u>M-4</u> <u>1877 SURVEY BY N.S. ANDREWS</u> SET STONE 8" HICK = S12 1/2°E 111 7/8 LKS. 5" APPLE = S62 1/2°E 74 7/8 LKS.	<u>ROAD COMMISSION - 1964</u> +D STONE IN MON. BOX FENCE TO EAST = N. 35.9' 25" B.O. = N29°E 43.95' TWIN WAL. = S28°E 40.55' A.P. = N43°W 32.2'	<u>1976 L.C.R.C. IN 3/005</u> PIPE IN MON. BOX WOOD FEN. POST = WEST 32.6' COR. IS IN CL MCCLISH RD. (SAYERS JOB #10048)
<u>1908 SURVEY BY MCCOY</u> STONE 12" HICK. = S12 1/2°E 111 7/8 LKS.	TELE. POLE = N43°W 47.4'	

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-4  
FD. 3/4" PIPE OVER +D STONE IN MON. BOX IN CL N-S RDWY & IN FENCE LINE TO WEST  
FENCE TO EAST IS NORTH 35.9'  
WOOD FENCE POST = WEST 32.6'

RATIFIED BY PEER GROUP  
IN ACCORDANCE WITH P.A. 345  
ON AUG. 14, 1995  
Wayne CO. REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-4  
SET 5/8"x24" IRON BAR W/STD. COUNTY CAP IN MON. BOX  
N&W IN S. SIDE A.P. = WEST 32.60'  
N&W IN S. SIDE P.P. = S88°W 33.45'  
N&W ON TOP A.P. = N43°E 49.45'  
N&W IN S. SIDE GATE POST = N59°W 37.09'  
CL ASPHALT = EAST 2.40'  
FENCE LINE TO EAST = NORTH 35.7', COR IS IN FENCE LINE TO WEST



LIBER 4 PAGE 160

Signed by Wayne A. Mostrom Date AUGUST 22, 1995  
Surveyor's Michigan License No. 14100