

FILED

Jun 27 12 46 PM '94

004 PG 031

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Cynthia A. Lematt
REGISTER OF DEEDS
ST. JOSEPH MICH

For corners in

ST. JOSEPH (County)

Located In:

Corner Code ##

PARK TWP.

- 1. Public Land Survey T 5 S R 11 W A-11
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R

Register of Deeds Stamp & File Number

- 4. Lot No. , Recorded Plat
5. Private Claims

Grid table with columns A-M and rows 2-13, containing numbers 1-36.

I, DAVID W. MOSTROM, in a field survey on APRIL 11, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(A-11) NW. COR. SEC. 31, T5S, R11W

BOOK A, PAGE 146

GLO

STAKE FROM ORIG. BRG. TREE
NO WITNESSES

INT. RANGE LINE 54 LKS. N. OF POST

Y. OAK 12" S10 1/2 E 45 LKS.

Y. OAK 18" N76 E 67 LKS.

SURVEY BY E.L. MINER IN NOV. 1925

BOOK A, PAGE 28

2" X 6' BOILER FLUE SET IN BRICK
NO WITNESSES

SWAMP W.O. STAKE SET AT INT. OF SEC. & RANGE LINES

6" HICKORY = S20 E 72 3/4 LKS.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(A-11)

FOUND 2" X 6' BOILER TUBE SURROUNDED BY BRICK

AS SET BY MINER. THERE ARE NO E-W OR N-S FENCES IN THE AREA.

SURVEY & REMONUMENTATION

AUG 31 1994

COMMISSION

RATIFIED BY PEER GROUP
IN ACCORDANCE WITH P.A. 345
ON APRIL 11th, 1994
CO. REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(A-11)

PLACED STANDARD CAP IN 2" X 6' BOILER TUBE

CORNER FALLS 35.64' NORTH OF NE COR. SEC. 36, T5S, R12W

PK NAIL & WASHER ON N. SIDE OF 10" OAK 2' HIGH = N45 E 16.08'

PK NAIL & WASHER ON N. SIDE OF 6" HICKORY 2' HIGH = N85 W 13.16'

PK NAIL & WASHER ON N. SIDE OF 8" HICKORY 2' HIGH = S45 W 11.41'



Signed by [Signature]

Date JUNE 14, 1994

Surveyor's Michigan License No. 32339

REMONUMENTATION