

NOV 04 1997

COMMISSION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 5 PAGE 16

For corners in

ST. JOSEPH	Located In:	Corner Code #
(County)		
PARK TWP.		
1. Public Land Survey	T 5S R 11W	B-9
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

STATE OF MICHIGAN  
ST. JOSEPH COUNTY  
FILED

17 SEP 97 3:24 P.M.

CYNTHIA JARRATT  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, DAVID W. MOSTROM, in a field survey on AUG. 9, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

(B-9) 1/4 CORNER COMMON TO SECTIONS 19 & 30, T5S R11W

- \*1876 SURVEY IN BK A, PG 28 STONE FROM OLD BEARINGS
- \*1944 SURVEY FOUND IRON BAR
- \*1900 SURVEY IN BK B, PG 52 STONE
- SE COR. CHURCH = NW 68.25'
- SW COR. HSE. = NE 52.8'
- B.O. STUMP = N40°E 18.48'
- SW COR. PORCH = NE 46.9'
- 8" MAPLE = S44 1/2°W 36.96'
- \*1963 ROAD COMMISSION
- STONE UNDER 1/2" PIPE IN MON. BOX

- SE COR. CHURCH = N68°W 67.45'
- SW COR. OLD STORE = N40°E 52.2'
- 20" MAPLE = S47°W 37.5'
- \*LCRC IN BK 2, PG 181
- 1/2" PIPE IN MON. BOX
- SW COR. HOUSE = N40°E 52.43'
- NW COR. HOUSE = S35°E 51.26'
- NE COR. HOUSE = S55°W 80.00'
- SE COR. CHURCH ENTRY = N55°W 66.7'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(B-9)  
FOUND 3/4" X 16" LONG PIPE OVER STONE 22" DEEP IN MON. BOX  
30" MAPLE = S44 1/2°W 36.96' (FACE OF ORIG. TREE)  
SE COR. CHURCH = N68°W 67.66'  
SW COR. HOUSE = N40°E 52.5'± (CUT STONE FOUNDATION)  
NW COR. HOUSE = S35°E 51.15'± (CUT STONE FOUNDATION)  
SE COR. CHURCH ENTRY = N55°W 66.7'  
CORNER FALLS 0.5' EAST OF 1/2 WILBUR ROAD AND 1.0' N. OF FENCELINE PROJ. TO WEST

RATIFIED BY PEER GROUP  
IN ACCORDANCE WITH P.A. 345  
ON AUGUST 11, 1997  
Way CO. REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(B-9) 1/4 CORNER COMMON TO SECTIONS 19 & 30, T5S R11W  
SET 5/8" X 16" IRON BAR W/STD. CAP OVER STONE IN MON. BOX  
SE COR. CHURCH = N68°W 67.66' (GROUND LEVEL)  
SE COR. CHURCH ENTRY = N55°W 66.70' (GROUND LEVEL)  
SW COR. HOUSE = N40°E 52.50' (GROUND LEVEL)  
NW COR. HOUSE = S35°E 51.15' (GROUND LEVEL)  
N & W 1.0' HIGH IN SE SIDE OF 30" MAPLE = S44°W 37.49'  
N & W 1.0' HIGH IN SW SIDE OF P. POLE = S30°E 39.50'



Signed by J. DW Mostrom DAVID W. MOSTROM  
Surveyor's Michigan License No. 32339

Date SEPTEMBER 8, 1997