

MAY 05 1995

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 4 PAGE 94

For corners in

ST. JOSEPH (County)

Located In:

Corner Code #

STATE OF MICHIGAN ST. JOSEPH COUNTY FILED

19 JAN 95 10:54 A.M.

CYNTHIA JARRATT REGISTER OF DEEDS

Register of Deeds Stamp & File Number

PARK TWP.

- 1. Public Land Survey T 5 S R 11 W C-1
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R

- 4. Lot No. Recorded Plat
5. Private Claims

I, DAVID W. MOSTROM, in a field survey on DECEMBER 7, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Grid table with columns A-M and rows 1-13. A dot is marked at the intersection of column C and row 2.

A. Description of original monument and accessories and/or subsequent restoration:

(C-1) NW COR. SEC. 5, T5S, R11W

G L O

10" W. OAK=N88 1/2°E 5.23 CHAINS GLO JOG ON FIELD NOTES TO SW COR SEC. 32, T4S, R11W=EAST 3.86 CH.
6" ASPEN=N35°E 3.57 CHAINS GLO JOG ON MAP TO SW COR SEC. 32, T4S, R11W=WEST 1.14 CHAINS

AFTER EVALUATING THE OTHER JOG DISTANCES ALONG THE COUNTY LINE, GLO TIES TO PHYSICAL FEATURES AND THE SECTION BREAKDOWN MEASUREMENTS, THE GLO JOG SHOWN ON THE MAP OF 1.14 CHAINS WAS FOUND TO BE CORRECT.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(C-1)

FOUND TILE AT SW COR. SEC. 32, T4S, R11W MEASURED EAST GLO JOG OF 75.24' AND EXCAVATED 10' X 10' AREA BUT COULD NOT FIND ANY EVIDENCE OF CORNER SET 5/8" X 24" IRON BAR W/STD. CAP IN 3/4" X 36" PIPE AT GLO JOG OF 75.24' BETWEEN THE TILE FOUND AT THE SW COR. & THE SOUTH 1/4 COR. OF SEC. 32, T4S, R11W.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(C-1) NW COR. SEC. 5, T5S, R11W

SET 5/8" X 24" IRON BAR W/STD. CAP IN 3/4" X 36" PIPE AT SOUTH SIDE OF OLD DITCH SW COR. SEC. 32, T4S, R11W (TILE) = WEST 75.24'
N & W 2.0' HIGH ON W. SIDE OF 10" POPLAR = N18°E 33.49'
N & W 2.0' HIGH ON E. SIDE OF 5" MAPLE = N05°W 32.78'
N & W 2.0' HIGH ON W. SIDE OF 12" POPLAR = N01°E 70.20'
N & W 3.0' HIGH ON NE SIDE OF 4" OAK = N49°W 23.13'

RATIFIED BY PEER GROUP IN ACCORDANCE WITH P.A. 345 ON DEC. 12, 1994 CO. REPRESENTATIVE

Signed by

J. D. W. Mostrom (Signature)

Date

JANUARY 6, 1995

Surveyor's Michigan License No. 32339

4/16/1995

REMONUMENTATION

LIBER 4 PAGE 94