

SURVEY & REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970 LIBER 4 PAGE 95

For corners in ST. JOSEPH (County)

Located In:

Corner Code #

STATE OF MICHIGAN ST. JOSEPH COUNTY FILED

19 JAN 95 10:54 A.M.

CYNTHIA JARRATT REGISTER OF DEEDS

Register of Deeds Stamp & File Number

- 1. Public Land Survey T 5S R 11W C-2
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R

- 4. Lot No. Recorded Plat
5. Private Claims

1. DAVID W. MOSTROM in a field survey on DECEMBER 12, 19 94 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(C-2) 1/4 CORNER COMMON TO SECTION 5 & 6

GLO

1974 SAYERS SURVEY & LCRC IN BOOK 3, PG. 20

BOTH WITNESSES GONE

SET 18" IRON BAR & CAP

DIRT ROAD = SOUTH 8'

8" OAK = SOUTH 22.35'

APPEARS TO HAVE BEEN SET PROPORTIONALLY BETWEEN THE NW COR & SW COR

10" OAK = S55°E 38.84'

32" OAK = N72°30'E 51.27'

DBL 30" OAK = N75°W 42.90'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(C-2)

FOUND 3/8" X 18" CAPPED IRON BAR

DIRT ROAD = SOUTH 7'±

FOUND OLD 8" OAK = SOUTH 22.35' (FACE)

FOUND STUMP OF OLD 10" OAK = S55°E 38.84' (FACE)

IRON FALLS 0.92' WEST & 1.47' N OF PROPORTIONAL DISTANCE BETWEEN NW COR & SW COR

ACCEPTED LOCATION OF IRON AS CORNER

RATIFIED BY PEER GROUP IN ACCORDANCE WITH P.A. 345 ON DEC. 12, 1994 Wam CO. REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(C-2) 1/4 CORNER COMMON TO SECTION 5 & 6

SET 5/8" X 24" IRON BAR W/STD CAP IN MON BOX IN PLACE OF IRON FOUND

N & W 1.0' HIGH IN N SIDE OF 16" OAK = S60°W 64.85'

N & W 1.0' HIGH IN N SIDE OF 16" OAK = S50°W 53.36'

N & W 1.0' HIGH IN W SIDE OF 14" OAK = S10°E 25.71'

FACE OF 7" GALV IRRIGATION PIVOT STOP POST = S09°E 62.19' (TO FACE)

DIRT ROAD = SOUTH 7'±



Signed by [Signature]

Date JANUARY 4, 1995

Surveyor's Michigan License No. 32339

REMONUMENTATION