

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970 LIBER 4 PAGE 99

For corners in **SURVEY & REMONUMENTATION**
 ST. JOSEPH COUNTY
 PARK TWP.
 1. Public Land Survey
 2. Property Controlling in Section
 3. Miscellaneous Property in Sec.
 4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

APR 10 1995
 COMMISSION

Located In: Corner Code #
 T 5S R 11W C-3
 T _____ R _____
 T _____ R _____
 T _____ R _____
 T _____ R _____
 S _____ T _____ R _____
 S _____ T _____ R _____
 S _____ T _____ R _____
 S _____ T _____ R _____

STATE OF MICHIGAN
 ST. JOSEPH COUNTY
 FILED
 23 JAN 95 9:22 A.M.
 CYNTHIA JARRATT
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

DAVID W. MOSTROM in a field survey on DECEMBER 12, 1994 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3		●										
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

(C-3) CORNER COMMON TO SECTIONS 5, 6, 7, 8
 GLO - BOTH WITNESSES TREES GONE LCRC IN BOOK 2, PG. 36- BOOK 3, PG. 20 -1974 SAYERS SURVEY
 1892 SURVEY IN BOOK A, PG. 666 SET IRON BAR IN REMAINS OF ORIGINAL STAKE FOUND
 NO DESCRIPTION OF CORNER 10" ELM = EAST 2.75'
 WITNESS GONE 12" HICKORY = SOUTH 2.39'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(C-3)
 FOUND 3/8" IRON BAR IN REMAINS OF FENCE TO SOUTH AND 1.0' SOUTH OF EAST-WEST FENCE
 14" ELM = EAST 2.75'
 16" HICKORY = SOUTH 2.39'

RATIFIED BY PEER GROUP
 IN ACCORDANCE WITH P.A. 345
 ON DEC. 12, 1994
 Warr CO. REPRESENTATIVE



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(C-3) CORNER COMMON TO SECTIONS 5, 6, 7, 8
 SET 5/8" X 24" IRON BAR W/STD. CAP IN PLACE OF 3/8" IRON BAR FOUND
 CORNER IS IN REMAINS OF FENCE TO SOUTH & 1.0' SOUTH OF EAST-WEST FENCE
 N & W 1' HIGH ON S. SIDE OF 14" ELM = EAST 2.75'
 N & W 1' HIGH ON E. SIDE OF 16" HICKORY = SOUTH 2.39'
 N & W 1' HIGH ON NW SIDE OF 12" OAK = S72°W 27.08'
 N & W 2' HIGH ON N. SIDE OF 12" ELM = S88°W 40.08'

LIBER 4 PAGE 99

Signed by [Signature] Date DECEMBER 14, 1994
 Surveyor's Michigan License No. 32339

REMONUMENTATION