

SURVEY & REMONUMENTATION

NOV 30 1993

004 PG 012

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

FILED

OCT 7 11 06 AM '93

REGISTER OF DEEDS

REGISTER OF DEEDS

or corners in **COMMISSION**

ST. JOSEPH

(County)

Located In:

Corner Code #

Public Land Survey T 5S R 11W C-4
 1/4 CQR., SEC. 7, T _____ R _____
 PARK TOWNSHIP T _____ R _____
 T _____ R _____
 Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____
 Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____

Register of Deeds Stamp & File Number

Lot No. _____, Recorded Plat _____
 Private Claims _____

WAYNE A. MOSTROM, in a field survey on SEPTEMBER 13, 19 93,
 hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned
 in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the
 current manual of survey instructions of the United States Department of the Interior, Bureau of Land
 Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5
 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a
 Court of Law; established, re-established, monumented, re-monumented, recovered, found as
 expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Description of original monument and accessories and/or subsequent restoration:

GLO 1966 SURVEY BY INGERSOLL
 6" B.O. = N54 1/2° E 57 LKS NOTHING FD.-SET 60 D NAIL
 5" B.O. = S64 1/2° W 42 LKS
1892 SURVEY BY TODD 1972 SURVEY BY WINTHER
 STO. FD.=ORIG. WITT. FD STO IN MON BOX IN FENCE
 STILL STANDING TO S. 4' S. OF \mathcal{C} IRON = SOUTH 33.0'
 6" B.O. = N56° E 59 LKS
 8" W.O. = N20 1/2° W 45 LKS

1973 SURVEY BY SMITH & LCRC
IN 1/23

STO IN MON BOX IN FENCE TO S
 84' S OF \mathcal{C} ; IRON=S 33.0'
LCRC IN 3/22 - 1974
 NOTCHED STO IN MON BOX
 PP=N51° E 42.2'
 18" HICK=S20° E 21.92'

Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FD 3/4" PIPE IN MON BOX
 P.P. = N50° E 42.23'
 IRON BAR 12" DEEP = SOUTH 33.04'

NOTE: COUNTY HAS IMPROVED ENTIRE ROAD IN RECENT YEARS. AREA IS NOW A 5' FILL-BOX WAS RAISED BY CO. ROAD COMM. - \mathcal{C} ALIGNMENT OF ROADWAY WAS CHANGED.



Description of monument for corner and accessories established to perpetuate locating the position of the corner:

5/8" X 24" IRON BAR SET W/STD. COUNTY CAP
 P.O. #132-6 = N50° E 42.23'
 P.P. #131-52 = S20° W 47.26'
 IRON BAR = SOUTH 33.04'
 N & W IN W. SIDE DBL. 28" OAK = N0° E 30.0'
 COR IS 1.5' N OF \mathcal{C} PAV'MT.

APPROVED BY PEER GROUP
 CORNER AS A PERPETUATION
 OF ORIG. CORNER.

Signed by Wayne A. Mostrom
 Surveyor's Michigan License No. 14100

Date SEPTEMBER 15, 1993 HISC. 7.00