

MAY 05 1995

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 4 PAGE 90

For corners in

ST. JOSEPH
(County)
PARK TOWNSHIP

Located In:

Corner Code #

- 1. Public Land Survey T 5S R 11W C-5
- T R
- T R
- T R
- 2. Property Controlling S T R
- in Section S T R
- 3. Miscellaneous S T R
- Property in Sec. S T R

STATE OF MICHIGAN
ST. JOSEPH COUNTY
FILED

19 JAN 95 10:51 A.M.

CYNTHIA JARRATT
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

- 4. Lot No. , Recorded Plat
- 5. Private Claims

I, DAVID W. MOSTROM, in a field survey on OCTOBER 7, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

(C-5) CORNER COMMON TO SECTIONS 7,8,17,18

GLO	1966 INGERSOLL SURVEY	1974 LCRC IN BK. 3, PG. 22
BOTH WITNESSES GONE	SET PK NAIL	1" IRON
1956 MDOT	4 WITNESSES ARE GONE	2 WITNESSES GONE BUT MATCH LCRC
UNABLE TO FIND CORNER	1973 SURVEY BY WENLEY SMITH	IN BK. 1, PG. 23
SET PK NAIL	& LCRC IN BK 1, PG. 23	
ALL WITNESSES GONE	IRON ROD	
	WITNESSES ARE GONE BUT	
	MATCH MDOT WITNESSES	

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(C-5)

FOUND 1" IRON BAR IN PROJ. OF FENCE TO SOUTH
FOUND NOTHING UNDER IRON
8' CUT IN ROADWAY TO NORTH & 4' CUT TO SOUTH
TIED INTO CORNERS ON WENLEY SMITH SURVEY TO VERIFY
THAT IT IS THE SAME CORNER

RATIFIED BY PEER GROUP
IN ACCORDANCE WITH P.A. 345
ON Nov. 14, 1994
CO. REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(C-5) CORNER COMMON TO SECTIONS 7,8,17,18

SET 5/8" X 24" IRON W/STD. CAP IN MON. BOX IN PLACE
OF 1" IRON BAR FOUND
N & W 3' HIGH ON SW SIDE OF 36" DBL. POPLAR = S40°E 98.50'
N & W 2' HIGH ON S. SIDE OF 14" ELM = N64°W 52.00'
N & W 1' HIGH ON W. SIDE OF P. POLE = N03°W 51.08'
N & W 3' HIGH ON N. SIDE OF P. POLE = S74°E 142.07'
CL OF ROAD = SOUTH 5.6'



Signed by *[Signature]*

Date JANUARY 3, 1995

Surveyor's Michigan License No. 32339

REMONUMENTATION

195 10 1995