

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Park Township

LIBER 6 PAGE 17

STATE OF MICHIGAN
 ST. JOSEPH COUNTY
 FILED

29 MAR 2000 10:11:36 AM

CYNTHIA L. JARRATT
 REGISTER OF DEEDS

<u>St. Joseph County</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>5S</u> R <u>11W</u>	<u>C-8</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, David W. Mostrom, in a field survey on March 8, 2000 do state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

(C-8) 1/4 CORNER COMMON TO SECTIONS 19 & 20, PARK TOWNSHIP

A. Description of original monument and accessories and/or subsequent restoration:

GLO
 8" Y. OAK = S43°W 31.02'
 6" Y. OAK = N40°E 4.62'

**SURVEY &
 REMONUMENTATION**

JAN 31 2001

SECTION

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND POINTED STONE 6" DEEP
 STONE FALLS IN LINE WITH FENCE TO SOUTH & IN LINE WITH
 FENCELINE PROJECTED TO EAST
 NW CORNER SECTION 20 = N00°20'41"W 2654.08'
 SW CORNER SECTION 20 = S00°24'14"E 2658.23'
 LOWERED STONE 2.5' DEEP & SET A 5/8" X 24" IRON BAR WITH STD. CAP OVER STONE



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

5/8" X 24" IRON BAR WITH STD. CAP
 CENTER OF IRRIGATION PUMP = NORTH 46.62'
 N & W IN NW SIDE OF 12" TWIN OAK = N34°E 29.15'
 N & W IN S. SIDE OF 30" OAK = S77°E 34.68'
 N & W IN SW SIDE OF 14" OAK = S58°E 35.95'
 N & W IN E. SIDE OF 24" HEDGE = S05°E 15.35'
 N & W IN SW SIDE OF 7" HICKORY = S35°E 4.80'

**RATIFIED BY PEER GROUP
 IN ACCORDANCE WITH P.A. 345
 ON MARCH 13, 2000
Wm CO. REPRESENTATIVE**

LIBER 6 PAGE 17

Signed by J.W. Mostrom David W. Mostrom Date March 23, 2000

Surveyor's Michigan License No. 32339

REMONUMENTATION