

JUN 27 12 47 PM '94

Cynthia A. Bennett
REGISTER OF DEEDS
ST. JOSEPH COUNTY

004 PG 044

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

ST. JOSEPH

Located In:

Corner Code 44

SURVEY & REMONUMENTATION COMMISSION
APR 10 1995

- 1. Public Land Survey T 5S R 11W D-5
T _____ R _____
T _____ R _____
T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____
- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, WAYNE A. MOSTROM in a field survey on NOV. 8, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- | | | | |
|----------------------------|------------|---------------------------------|-----------------------------------------------------|
| <u>D-F</u> | <u>GLO</u> | <u>1966 SURVEY BY INGERSOLL</u> | <u>1973 L.C.R.C. (1/22) & 1973 SMITH SURVEY</u> |
| 6" B.O. N75°E | 28 LKS | FOUND IRON ROD | |
| 6" B.O. N44°W | 24 LKS | | SEE SAME WITH SHOWN FOR 1972 SURVEY |
| <u>1906 SURVEY BY REED</u> | | <u>1972 SURVEY BY WINTHER</u> | |
| NOTCHED STONE | | 1/4" SPIKE IN MON. BOX | <u>1974 SURVEY & L.C.R.C. IN 3/22</u> |
| 3" B.O. = S18°W 90 LKS | | P.P. N35°W 40.9' | GROOVED STONE IN MON. BOX |
| 2" B.O. = S64°E 771/8 LKS | | 18" OAK = N60°E 43.7' | 12" OAK = N64°E 43.79' |
| | | 16" OAK = S70°E 50.8' | 15" OAK = S65°E 50.9' |
| | | FEN. COR. = S45°W 45.5' | |


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- D-5
15" OAK = S65°E 50.9' OR 771/8 LKS
16" OAK = S70°E 50.8'
FOUND NOTCHED STONE IN MON. BOX

RATIFIED BY PEER GROUP
IN ACCORDANCE WITH P.A. 345
ON Nov. 8th, 1993
W.A.M. CO. REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- D-5 (1/4 COR. BET. SEL'S 8 & 17)
SET 5/8" X 24" BAR & STD. CAP OVER
NOTCHED STONE IN MON. BOX
SW COR. BRICK HSE. = N37°E 129.10'
N & W IN N. SIDE 30" OAK = S63°E 50.88'
N & W IN S. SIDE P.P. = N50°W 57.92'
N & W IN E. SIDE P.P. = N29°W 46.45'



Signed by Wayne A. Mostrom
Surveyor's Michigan License No. 14100

Date 5.24.94

REMONUMENTATION