

LAND CORNER RECORDATION CERTIFICATE  
 Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 6 PAGE 18

For corners in Park Twp.

St. Joseph Located In: Corner Code #  
 (County)

STATE OF MICHIGAN  
 ST. JOSEPH COUNTY  
 FILED

29 MAR 2000 10:12:08 AM

CYNTHIA L. JARRATT  
 REGISTER OF DEEDS

1. Public Land Survey T 5S R 11W D-7  
 T R  
 T R  
 T R  
 T R  
 2. Property Controlling S T R SURVEY &  
 in Section S T R REMONUMENTATION  
 3. Miscellaneous S T R  
 Property in Sec. S T R JAN 31 2001

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_ SECTION  
 5. Private Claims \_\_\_\_\_

I, Wayne A. Mostrom, in a field survey on Sept. 8, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7			19		20		21		22		23	
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

<u>Road Comm. - 1960's</u> Stone Tri.-Oak = NW 66' Oak = SE 71.4'	<u>Sayers 1972 Survey</u> Shows cor. 2657.13' N. of center & 2653.62' W. of NE cor. Sec. 20	<u>Sayers 1973 Survey</u> Box over pipe Rd. Stgn = SE 51.1' Rd. Stgn = SW 40.7' P.P. = NW 56'	<u>Mostrom 1996 Survey</u> 3/4" pipe over sto. in box Replaced pipe w/5/8" bar 44" Oak = S24°E 71.4' 22" Oak = S66°E 82.42' P.P. = N35°W 56.55' 6" Post = S46°W 48.97'
--	--	---	--

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 5/8" x 18" bar over stone 34" deep in Mon. box  
 ☐ roadway = West 0.9'  
 Cor. is in ☐ of E-W rdwy.  
 44" Oak = SE 71.4'  
 P.P. = NW 56' & 56.55'  
 22" Oak = S66°E 82.42'

RATIFIED BY PEER GROUP  
 IN ACCORDANCE WITH P.A. 345  
 ON SEPT. 13, 2000 1999  
Wayne CO. REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 5/8" x 24" Bar w/std. cap. over stone in Mon. Box  
 N & W in W. Side 48" Oak = S24°E 71.40'  
 N & W in N. Side 26" Oak = S66°E 82.42'  
 N & W in NE Side P.P. = N35°W 56.55'  
 N & W in W. Side 36" Oak = S20°E 90.99'



LIBER 6 PAGE 18

Signed by Wayne A. Mostrom Wayne A. Mostrom Date March 15, 2000  
 Surveyor's Michigan License No. 14100

REMONUMENTATION