

SURVEY & REMONUMENTATION

JAN 31 2001

SECTION

LAND CORNER RECORDATION CERTIFICATE LIBER 6 PAGE 19
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
ST. JOSEPH COUNTY
FILED

29 MAR 2000 10:12:54 AM

CYNTHIA L. JARRATT
REGISTER OF DEEDS

For corners in Park Township

<u>St. Joseph County</u> <small>(County)</small>	Located In:	Corner Code #	
1. Public Land Survey	T ___ R ___	_____	_____
	T ___ R ___	_____	_____
	T ___ R ___	_____	_____
	T ___ R ___	_____	_____
2. Property Controlling in Section	S <u>20</u> T <u>5S</u> R <u>11W</u>	<u>D-8</u>	_____
	S ___ T ___ R ___	_____	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____	_____
	S ___ T ___ R ___	_____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, David W. Mostrom, in a field survey on March 8, 2000, do state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

(D-8) CENTER SECTION 20, PARK TOWNSHIP

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

<p>1972 SAYERS SURVEY CORNER NOT LABELED OR WITNESSED</p> <p>1973 KESTER SURVEY 3/4" PIPE IN MONUMENT BOX</p> <p>1983 MOSTROM SURVEY FOUND 3/4" PIPE IN MONUMENT BOX 12" HICKORY = S47°E 43.80' 16" HICKORY = S87°E 41.47' P. POLE = N77°W 35.18'</p>	<p>1999 MOSTROM SURVEY FOUND 1" PIPE 12" DEEP IN GRAVEL ROADWAY 16" HICKORY = S47°E 43.80' 22" HICKORY = S87°E 41.47' 50" TRIPLE OAK = N45°E 44.83' P. POLE = N83°W 35.18'</p> <p>ROAD COMMISSION (NO DATE) THIS CORNER WAS DUG FOR BY HAND BUT NOT FOUND</p>
--	---

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1" PIPE 14" DEEP IN MONUMENT BOX IN CENTERLINE OF BUCKHORN ROAD
16" HICKORY = S47°E 43.80'
22" HICKORY = S87°E 41.47'
50" TRIPLE OAK = N45°E 44.83'
P. POLE = N83°W 35.18'
CORNER FALLS IN LINE WITH FENCES TO THE EAST & WEST
CORNER FALLS 0.65' NORTH & 0.09' EAST OF INT. OF 1/4 LINES
SET 5/8" X 24" IRON BAR WITH STD. CAP IN 1" PIPE IN MONUMENT BOX

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

5/8" X 24" IRON BAR WITH STD. CAP IN MONUMENT BOX
N & W IN SE SIDE OF 50" TRIPLE OAK = N45°E 44.83'
N & W IN N. SIDE OF 22" HICKORY = S87°E 41.47'
N & W IN SW SIDE OF 16" HICKORY = S47°E 43.80'
N & W IN S. SIDE OF P. POLE = N83°W 35.18'
N & W IN S. SIDE OF P. POLE = S71°E 58.52'



**RATIFIED BY PEER GROUP
IN ACCORDANCE WITH P.A. 345
ON MARCH 13, 2000
WILSON CO. REPRESENTATIVE**

Signed by J. D. W. Mostrom David W. Mostrom Date March 23, 2000
Surveyor's Michigan License No. 32339

REMONUMENTATION

LIBER 6 PAGE 17