

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER **6** PAGE **20**

STATE OF MICHIGAN
 ST. JOSEPH COUNTY
 FILED

29 MAR 2000 10:13:12 AM

CYNTHIA L. JARRATT
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

For corners in Park Twp.

St. Joseph Located In: Corner Code #
 (County)

1. Public Land Survey T 5S R 11W D-9
 T R
 T R
 T R
 2. Property Controlling S T R SURVEY &
 in Section S T R REMONUMENTATION
 3. Miscellaneous S T R
 Property in Sec. S T R JAN 31 2001

4. Lot No. _____, Recorded Plat _____ SECTION _____
 5. Private Claims _____

I, Wayne A. Mostrom, in a field survey on Sept. 8, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9		0											
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

<u>J. White 1955 Survey</u> Stone <u>Road Comm. 1960's</u> ½" pipe over +d stone in Mon. box	<u>Sayers 1972 Survey</u> Pipe in Mon. box 24" Oak - NW 63.3' 24" Cherry - SW 70' Road sign - SE 53.8' <u>Kester 1973 Survey</u> ½" pipe in Mon. box	<u>Sayers 1974 Survey</u> Sto. in Mon. box 30" Wal. - NE 30.15' 18" Oak - SE 47' <u>Sayers 1979 Survey</u> 20" Wal. - SE 82.52' 30" Oak - NW 64.29' Pole - SW 62.06'	<u>1983 LCRC In 2/161</u> ½" bar over sto. in box 30" Oak - N67°W 64.25' 30" Cherry - S18°W 71'
--	--	---	--

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 3/4" x 8" pipe over +d stone 11" deep in Mon. box
 C E-W rdwy - South 2.50'
 C rdwy to South - East 3.70'
 C rdwy to North - East 1.4'
 20" Wal. = SE 82.52'
 Pole = SW 62.06'

RATIFIED BY PEER GROUP
 IN ACCORDANCE WITH P.A. 345
 ON SEPT, 13, 1999
Wayne CO. REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 5/8" X 8" Iron w. Std cap in conc. over stone in Mon. Box
 N & W in S. side Tele. Pole = S60°W 62.08'
 N & W in NW side 60" Maple = N35°E 74.02'
 Conc. R.O.W. Mon. = N45°E 46.51'
 N & W in N. side 30" Wal. = S71°E 82.95'



Signed by Wayne A. Mostrom
 Surveyor's Michigan License No. 14100

Date March 15, 2000

REMONUMENTATION

LIBER 6 PAGE 20