

MAY 05 1995

COMM

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 4 PAGE 97

For corners in

ST. JOSEPH
(County)

Located In:

Corner Code #

STATE OF MICHIGAN
ST. JOSEPH COUNTY
FILED

19 JAN 95 10:55 A.M.

CYNTHIA JARRATT
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

- PARK TWP.
- 1. Public Land Survey T 5S R 11W D-13
 - T R
 - T R
 - T R
 - 2. Property Controlling S T R
 - in Section S T R
 - 3. Miscellaneous S T R
 - Property in Sec. S T R

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, WAYNE A. MOSTROM in a field survey on DECEMBER 19, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

D-13 GLO

1974 SURVEY BY MOSTROM & LCRC IN 3/27

7" W.O. = N67°E 24 LKS
7" W.O. = N37°W 40 LKS

STONE W/GRADER BLADE 12" DEEP
P.P. = N7°25'W 24.65'
28" LOCUST = N60°E 46.45'
W. EDGE/PAV'MT = EAST 16.86'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

D-13

P.P. = N7°25'W 24.65'
W. EDGE PAV'MT = EAST 16.86'
FD. STONE WITH 5" PIPE OVER IT & 3 GRADER BLADES
JOG MEAS. 61.02'

RATIFIED BY PEER GROUP
IN ACCORDANCE WITH P.A. 345
ON NOV. 8, 1993 + JAN 9, 1995
CO. REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-13 SOUTH 1/4 COR. SEC. 32

SET 5/8" X 24" BAR W/STD. CAP
EDGE PAV'MT = NE 16.55'
MON. BOX (TWP. JOG) = EAST 61.02'
N & W IN POWER POLE = N5°W 24.98'
SE COR. BRICK HSE = N45°W 126.71'
CL OF 6" MAPLE = N20°W 37.80'
CL OF 4" PINE = WEST 15.45'



Signed by *Wayne A. Mostrom*

Date JANUARY 10, 1995

Surveyor's Michigan License No. 14100

REMONUMENTATION

6th 10 1995

LIBER 4 PAGE 97