

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

FILED

JUN 27 12 40 PM '94

004 PG 046

Cynthia E. Bennett

REGISTER OF DEEDS
ST. JOSEPH MICH

For corners in

ST. JOSEPH
(County)

Located In:

Corner Code #

PARK TWP.

1. Public Land Survey T 5 S R 11 W E-4

T _____ R _____

T _____ R _____

T _____ R _____

2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

**SURVEY &
REMONUMENTATION**

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

AUG 3 1 1994

5. Private Claims _____

COMMISSION

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8	⊕	9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, WAYNE A. MOSTROM, in a field survey on NOVEMBER 8, 19 93

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO

7" W.O. = S70°W 16 LKS.

7" W.O. = N49½°E 46 LKS.

L.C.R.C. (3/22) & 1974 SURVEY BY MOSTROM

1966 SURVEY BY INGERSOLL

STONE IN MON. BOX

10" OAK = N45°E 75.69'

F. POST = SOUTH 24.5'

T. POLE = S30°W 24.33'

FOUND STONE IN MON. BOX

TREE = N75°E 75.84'

SPIKE @ BASE OF R.R. TIE POST = SOUTH 24.75'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

30" BLK. OAK = N75°E 75.84'

R.R. TIE POST = SOUTH 24.75'

FOUND STONE IN MON. BOX

RATIFIED BY PEER GROUP
IN ACCORDANCE WITH P.A. 345
ON Nov. 8, 1993
Wayne CO. REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-4 (¼ COR. COMMON TO SECTIONS 8 & 9)

N. & W. IN 30" BLK. OAK = N75°E 75.84'

N. & W. IN R.R. TIE POST = SOUTH 24.84'

COR. IS 2' N. OF ⊕ ASPHALT ROAD & IN FENCE LINE TO N. & S.

N. & W. IN 14" SPRUCE = S45°W 43.42'

N. & W. IN POWER POLE = N45°E 219.45'

SET 5/8" X 12" IRON BAR IN CONC. OVER STONE



Signed by Wayne A. Mostrom

Date 6/16/94

Surveyor's Michigan License No. 14100

REMONUMENTATION