

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 LIBER **6** PAGE **22**

For corners in Park Township

St. Joseph County Located In: Corner Code #
 (County)

STATE OF MICHIGAN
 ST. JOSEPH COUNTY
 FILED
 29 MAR 2000 10:13:56 AM
 CYNTHIA L. JARRATT
 REGISTER OF DEEDS

1. Public Land Survey T 5S R 11W E-8
 T _____ R _____
 T _____ R _____
 T _____ R _____
 T _____ R _____
 2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____
 3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____

**SURVEY &
 REMONUMENTATION**
 JAN 31 2001

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

SECTION

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, David W. Mostrom, in a field survey on March 2, 20 00, do state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

(E-8) 1/4 CORNER COMMON TO SECTIONS 20 & 21, PARK TOWNSHIP

A. Description of original monument and accessories and/or subsequent restoration:

GLO 1977 SAYERS SURVEYS
 8" W. OAK = N60°W 21.12'
 7" W. OAK = S72°E 16.5'
 CORNER USED ON SURVEYS
 BUT NOT LABELED OR WITNESSED

1972 SAYERS SURVEY
 EXCAVATED AREA AROUND FENCE
 POST - FOUND NOTHING
 SET CAPPED IRON MIDWAY & ON LINE BETWEEN SECTION CORNERS



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND CAPPED IRON #7874 AS SET BY SAYERS IN 1972.
 WITNESSED IRON & EXCAVATED AREA 5' X 5' X 2' DEEP BUT
 FOUND NO EVIDENCE OF EXISTING STAKE OR STONE.
 IRON FOUND FALLS AT INTERSECTION OF TREE LINES & FENCE REMAINS
 TO NORTH, SOUTH & WEST.
 SET 5/8" X 48" IRON BAR WITH STD. CAP IN PLACE OF CAPPED IRON FOUND.
 NE CORNER SECTION 20 = N00°30'08"W 2658.31', SE CORNER SECTION 20 = S00°30'53"E 2656.30 FEET

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

5/8" X 48" IRON BAR WITH STD. CAP
 N & W IN SW SIDE OF 36" OAK = S45°E 9.87'
 N & W IN W. SIDE OF 6" HICKORY = N10°E 5.93'
 N & W IN SE SIDE OF 7" CHERRY = S45°W 28.80'
 N & W IN N. SIDE OF 34" HICKORY = N85°W 24.76'
 N & W IN W. SIDE OF 30" OAK = S02°E 30.02'

RATIFIED BY PEER GROUP
 IN ACCORDANCE WITH P.A. 345
 ON March 13, 2000
Wau CO. REPRESENTATIVE

Signed by J. O. W. Mostrom David W. Mostrom Date March 23, 2000
 Surveyor's Michigan License No. 32339

REMONUMENTATION

LIBER 6 PAGE 22