

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 6 PAGE 23

For corners in Park Township

St. Joseph County Located In: Corner Code #
 (County)

STATE OF MICHIGAN
 ST. JOSEPH COUNTY
 FILED

29 MAR 2000 10:14:15 AM

CYNTHIA L. JARRATT
 REGISTER OF DEEDS

1. Public Land Survey T 5S R 11W E-9
 T R
 T R SURVEY &
 T R REMONUMENTATION
 2. Property Controlling S T R
 in Section S T R
 3. Miscellaneous S T R
 Property in Sec. S T R
 SECTION

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, David W. Mostrom, in a field survey on March 8, 2000 do state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

(E-9) CORNER COMMON TO SECTIONS 20, 21, 28, 29 PARK TOWNSHIP

A. Description of original monument and accessories and/or subsequent restoration:

GLO
 8" W. OAK = N48°W 1.32'
 6" W. OAK = S31°W 18.48'
 1904 SURVEY IN BOOK B, PAGE 110
 STONE
 14" B. WALNUT = N38°E 30.20'
 24" B. WALNUT = N71°E 73.92'
 1879 SURVEY IN BOOK A, PAGE 304
 SET 14" X 8" X 6" STONE MARKED +
 FROM THE REMAINS OF THE OLD BRG. TREES
 3" WALNUT = N38°E 30.86'
 8" WALNUT = N71°E 74.58'
 1972 SAYERS SURVEY
 BOX OVER STONE
 30" WALNUT = NE 30.15'
 FENCE CORNER = NW 34.35'
 W. OAK = SE 47.0'
 1979 LCRC IN BOOK 2, PAGE 118
 FOUND STONE IN MON. BOX
 30" WALNUT = N40°E 32.03'
 40" OAK = S45°E 49.45'
 4" CEDAR = N10°W 52.69'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND NOTCHED STONE 9" DEEP IN MONUMENT BOX
 36" WALNUT = N40°E 30.86'
 48" OAK = S45°E 49.45'
 10" CEDAR = N10°W 52.69'
 CENTERLINE MOOREPARK ROAD = SOUTH 1.5'
 SET 5/8" X 6" IRON BAR WITH STD. CAP IN CONCRETE OVER STONE IN MONUMENT BOX



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

5/8" X 6" IRON BAR WITH STD. CAP IN MONUMENT BOX
 SW CORNER HOUSE FOUNDATION = N25°E 88.15'
 N & W IN NW SIDE OF 40" WALNUT = N37°E 31.08'
 N & W IN E. SIDE OF 10" CEDAR = N12°W 52.65'
 N & W IN E. SIDE OF 11" CHERRY = S27°W 32.98'
 N & W IN SW SIDE OF 50" OAK = S52°E 49.41'

RATIFIED BY PEER GROUP
 IN ACCORDANCE WITH P.A. 345
 ON MAR. 13, 2000
Wheeler CO. REPRESENTATIVE

Signed by J. W. Mostrom David W. Mostrom Date March 23, 2000
 Surveyor's Michigan License No. 32339

REMONUMENTATION

LIBER 6 PAGE 23