

MAY 05 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 4 PAGE 119

For corners in

<u>ST. JOSEPH</u> (County)	Located In:	Corner Code \neq
<u>PARK TWP.</u> 1. Public Land Survey	<u>T 5 S R 11 W</u>	<u>1-7</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

STATE OF MICHIGAN
ST. JOSEPH COUNTY
FILED

11 APR 95 2:12 P.M.

CYNTHIA JARRATT
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, WAYNE A. MOSTROM, in a field survey on MARCH 24, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

I-7 1976 SURVEY BY SAYERS &
L.C.R.C. IN L-3, PG. 26

FOUND STONE
24" W.O. = N23°E 72.8'
ROAD SIGN = S41°E 41.1'
24" W.O. = S17°W 114.50'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-7
FD. +1D STONE IN MON. BOX IN \oslash OF N-S RDWY & 2' SOUTH OF
E-W RDWY.
36" W.O. = N23°E 72.8'
33" W.O. = S17°W 114.5'

RATIFIED BY PEER GROUP
IN ACCORDANCE WITH P.A. 345
ON April 10, 1995
W.A. Mostrom CO. REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-7 SET 5/8" X 7" IRON IN CONC. OVER STONE FOUND
N & W ON W. SIDE 36" OAK = N20°E 73.90'
N & W ON NW SIDE G.P. CO. POLE #35737 = N60°E 168.64'
N & W ON E. SIDE 6" OAK = S30°W 90.75'
1/2" X 18" IRON BAR = S45°W 46.45'
COR. IS IN CL N-S RDWY & 2' SOUTH OF E-W RDWY.



LIBER 4 PAGE 119

Signed by Wayne A. Mostrom Date 4/11/95
Surveyor's Michigan License No. 14100

REMONUMENTATION