

SURVEY & REMONUMENTATION

MAY 05 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 LIBER 4 PAGE 121

For corners in

ST. JOSEPH (County)	Located In:	Corner Code #
PARK TWP.	T 5 S R 11 W	J-7
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

STATE OF MICHIGAN
ST. JOSEPH COUNTY
FILED

11 APR 95 2:13 P.M.

CYNTHIA JARRATT
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, WAYNE A. MOSTROM, in a field survey on MARCH 24, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7									●				
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

<u>J-7</u> 1885 SURVEY BY TODD	1966 ROAD COMM. NOTES	1977 L.C.R.C. IN L-3, PG. 25
SET OAK POST IN REMAINS OF OLD STAKE & OVER IT A STONE	FD. POINTED STONE OVER WOOD STAKE IN MON. BOX	BY SAYERS
BOTH ORIG. WITNESS TREES WERE IN PLACE	DBL. BLK. OAK=N69°W 51.97'	BOX OVER PIPE
	ANCHOR POST = N2°E 26.27'	30" W.O. = NW 26.5'
	28" HICK. = N56°E 44.64'	R.R. RAIL = NORTH 27'
		38" W.O. = SOUTH 24'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

J-7
FD. POINTED STONE IN MON. BOX
BLK. OAK STUMP = N69°W 51.97'
28" HICK. = N56°E 44.64'
R.R. RAIL = NORTH 27'
W.O. STUMP = SOUTH 24'
COR. IS IN FENCE LINE TO N. & TREE LINE TO S.
COR. FALLS IN E-W RDWY.

RATIFIED BY PEER GROUP
IN ACCORDANCE WITH P.A. 345
ON April 10, 1995
Wayne A. Mostrom CO. REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-7 SET 5/8" X 24" BAR & STD. CAP OVER STONE IN MON. BOX
N & W IN W. SIDE 6" MULBERRY = N10°W 55.50'
N & W IN E. SIDE 8" CHERRY = N02°W 63.12'
N & W IN S. SIDE C.P. CO. POLE #640 = N78°W 144.12'
N & W IN NE SIDE 18" LOCUST = S54°E 83.45'
COR. IS IN CL E-W RDWY & IN FENCE LINE TO N. & S.
PAINT "+'' ON RR RAIL = NORTH 27.00'
NOTE: ALL NAILS & WASHERS ARE 24" ABOVE GRADE



Signed by Wayne A. Mostrom Date 4/11/95
Surveyor's Michigan License No. 14100

REMONUMENTATION

LIBER 4 PAGE 121