

LAND CORNER RECORDATION CERTIFICATE  
 Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 4 PAGE 226

For corners in ST JOSEPH Located in: \_\_\_\_\_ Corner Code # \_\_\_\_\_  
 (County)

1. Public Land Survey T 5S R 11W K-4  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

STATE OF MICHIGAN  
 ST. JOSEPH COUNTY  
 FILED

18 JUN 96 9:13 A.M.

CYNTHIA JARRATT  
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, Donald C. Andrews, in a field survey on MAY 30, 1996, do hereby certify that under requirements of P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO POST  
 1878 BK A, P 275 STONE  
 1975 SAYERS #9666 STONE IN BOX PP N88°E 36.16', AP N89°W 32.3'  
 1979 SAYERS #11303 MON BOX/STONE&PIPE  
 MC COY 'S BK 2, P 73 SHOWS STONE NO WITNESS  
 1986 MOSTROM FD 3/4" PIPE IN MON BOX WIT 8" HICK. NE 48.50, IRON BAR W'LY 33', PP NE 36.15'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 3/4" PIPE X 19" IN MON BOX. BELOW PIPE FOUND POINTED STONE SET 5/8"X24" IRON OVER STONE. REMON PEER GROUP ACCEPTED STONE AS CORNER POINT. SET 5/8" IRON OVER POINTED STONE AND RESET MON BOX.

SURVEY &  
 REMONUMENTATION

OCT 03 1996

COMMISSION

RATIFIED BY PEER GROUP  
 IN ACCORDANCE WITH P.A. 345  
 ON MAY 13, 1996  
W. J. JARRATT CO. REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

5/8" IRON X 24" WITH STANDARD ALUM. CAPPED :  
 6" OAK WEST 38.20'  
 A.P. S45°E 36.75'  
 U.P. N55°E 36.16'  
 12" HICKORY N80°E 48.63'



Signed by Donald C. Andrews  
 Donald C. Andrews, P.S.

Date 5/31/96

Surveyor's Michigan License No. 33967

LIBER 4 PAGE 226