

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in St. Joseph Located In: _____ Corner Code # _____
 (County)

1. Public Land Survey T 5S R 11W K-7
 T _____ R _____
 T _____ R _____
 T _____ R _____

2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

STATE OF MICHIGAN
 ST. JOSEPH COUNTY
 FILED

18 JUN 96 9:16 A.M.

CYNTHIA JARRATT
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, Donald C. Andrews, in a field survey on May 30, 1996, do hereby certify that under requirements of P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO POST
 1878 BK A, P 275 STONE & STAKE FROM OLD BEARINGS
 1961 SAYERS FOUND STAKE SURROUNDED BY STONES SET MON BOX
 1971 SAYERS NOTES SHOWS SE CORNER SEC. 14
 SAYERS INDEX SHOWS FOUND PIPE IN MON BOX
 1986 MOSTROM SHOWS FOUND PIPE IN MON BOX RR RAIL NW 28' & AP NE 42.3'

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 5/8" IRON X 16" DRIVEN THRU REMAINS OF STAKE SURROUNDED BY STONES IN MON. BOX. REMOVED IRON AND RESET 5/8" X 24" IRON THRU STAKE AND RESET MON. BOX

SURVEY &
 REMONUMENTATION


OCT 03 1996

COMMISSION

RATIFIED BY PEER GROUP
 IN ACCORDANCE WITH P.A. 345
 ON May 13, 1996
Wagon CO. REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

5/8"X24" IRON WITH STANDARD ALUM. CAP:
 40" MAPLE N45°W 44.73'
 PETRO. PIPELINE RIZER (AT GROUND) S45°W 46.22'
 N'LY SIGN POST S45°E 61.70'
 A.P. N45°E 41.60'



Signed by Donald C. Andrews
 Donald C. Andrews, P.S.
 Surveyor's Michigan License No. 33967

Date 5/31/96