

**SURVEY & REMONUMENTATION**

MAY 05 1995

COMMISSION

**LAND CORNER RECORDATION CERTIFICATE**

Filing Requirement of Act 74, Mich. P.A. 1970 LIBER 4 PAGE 122

For corners in

<u>ST. JOSEPH</u> (County)	Located In:	Corner Code #
PARK TWP.	T <u>5S</u> R <u>11W</u>	<u>M-8</u>
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

STATE OF MICHIGAN  
ST. JOSEPH COUNTY  
FILED

12 APR 95 3:15 P.M.

CYNTHIA JARRATT  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, WAYNE A. MOSTROM, in a field survey on APRIL 11, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

**M-8**

**ROAD COMMISSION - 1960'S**

LARGE STONE UNDER 1/2" PIPE  
IN MON. BOX  
R.R. RAIL = SOUTH 29.0'  
3" BOX ELDER = N55°W 34.25'  
SE COR. HSE. = N22°W 71.50'

**1977 SURVEY BY SAYERS**

PIPE IN MON. BOX  
R.R. RAIL = SOUTH 29'  
SE COR. HSE. = N22°W 71.5'  
3" BOX ELDER = N55°W 34.25'  
IRON BAR @ MENDON COR. =  
SOUTH 16.17'

**1986 SURVEY BY MOSTROM**

PIPE IN MON. BOX  
SE COR. HSE. = N22°W 71.5'  
IRON BAR @ MENDON COR. = S. 16.17'  
R.R. RAIL = NORTH 10.7'  
10" WAL. = SE 31.5'

**L.C.R.C. IN 2/268 BY ANDREWS**

SAME REF.'S AS ROAD COMMISSION

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


FOUND 3/4" X 10" PIPE OVER STONE IN MON. BOX  
FOUND IRON BAR @ MENDON COR. 16.17' SOUTH  
SE COR. HOUSE = N22°W 71.50'

RATIFIED BY PEER GROUP  
IN ACCORDANCE WITH P.A. 345  
ON April 10, 1995  
W.A.M. CO. REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

**M-8**

SET 5/8" X 10" IRON BAR WITH STD. CAP IN MON. BOX OVER STONE  
MENDON COR. = SOUTH 16.17' (IRON BAR)  
SE COR. HOUSE = N22°W 71.50'  
PAINT MARK ON S. SIDE R.R. RAIL POST = NORTH 10.65'  
CL GRAVEL RDWY. = SOUTH 7.0'  
N & W IN NW SIDE 8" PINE = N18°E 47.84'  
N & W IN S. SIDE OF POWER POLE = N70°W 119.46'



Signed by Wayne A. Mostrom Date APRIL 12, 1995  
Surveyor's Michigan License No. 14100