

**SURVEY &  
REMONUMENTATION**

**JUL 16 1998**

**SECTION**

**LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

**LIBER 5 PAGE 63**

For corners in

<u>ST. JOSEPH</u> (County)	Located In:	Corner Code #
FLOWERFIELD TWP. 1. Public Land Survey	T <u>5S</u> R <u>12W</u>	<u>A-5</u>
	T <u>    </u> R <u>    </u>	<u>    </u>
	T <u>    </u> R <u>    </u>	<u>    </u>
	T <u>    </u> R <u>    </u>	<u>    </u>
2. Property Controlling in Section	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>
	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>
3. Miscellaneous Property in Sec.	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>
	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>

STATE OF MICHIGAN  
ST. JOSEPH COUNTY  
FILED

22 Apr 1998 3:43:34 PM

CYNTHIA L. JARRATT  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, WAYNE A. MOSTROM, in a field survey on APRIL 6, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

<u>GLO</u>	<u>1871 SURVEY IN A/180</u>
SET POST 2.17 CHAINS N. OF CASS CO. CORNER 8" BEECH = N35°E 7 LKS	STAKE SET BY GREEN BEARING <u>1880'S SURVEY IN A/548</u> SET IRON LANDSIDE FROM CASS CO. COR. TO SEC. 12 & 13 AT 2.17 CH. N. 24" W.O. = N4 3/4° 19 LKS (COULDN'T FIND EXIST. CORNER)

APRIL 1998 BY ROAD COMM.  
PRO-RATED STONES FOUND 1/4 &  
1/2 MILE EAST & FOUND GOOD  
LOOKING, UPRIGHT IRON LANDSIDE  
LESS THAN 1 FOOT FROM PRO-RATED  
DISTANCE FROM THE EAST.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND IRON LANDSIDE UPRIGHT - POINTED END IS UP AT APPROX.  
20.33 CH. W. OF 1/2-1/4 COR. TO THE EAST PER OLD SURVEY IN BK 1, PG 180

RATIFIED BY PEER GROUP  
IN ACCORDANCE WITH P.A. 345  
ON April 13, 1998  
Wayne CO. REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET 5/8" X 48" IRON BAR W/STD. COUNTY CAP IN  
PLACE OF IRON LANDSIDE  
N & W IN W. SIDE 22" OAK = N10°E 4.78'  
N & W IN N. SIDE 8" ELM = S40°E 8.29'  
N & W IN E. SIDE 8" MAPLE = SOUTH 24.20'  
N & W IN E. SIDE 10" ELM = S40°W 5.25'  
N & W IN N. SIDE 8" MAPLE = WEST 2.38'



Signed by Wayne A. Mostrom  
Surveyor's Michigan License No. 14100

Date 4/17/98