

SURVEY & REMONUMENTATION

NOV 30 1993

COMMISSION

004 PG 007

FILED

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

JUL 27 1 03 PM '93

Cynthia R. Smatt

REGISTER OF DEEDS
 ST. JOSEPH CO MICH

corners in

JOSEPH (County) Located In: Corner Code: #/ #
 OWERFIELD TWP. Public Land Survey T 5S R 12W G-7
 T ___ R ___
 T ___ R ___
 T ___ R ___
 Property Controlling S ___ T ___ R ___
 in Section S ___ T ___ R ___
 Miscellaneous S ___ T ___ R ___
 Property in Sec. S ___ T ___ R ___

Register of Deeds Stamp & File Number

Lot No. _____, Recorded Plat _____
 Private Claims _____

WAYNE A. MOSTROM, in a field survey on JUNE 14, 1993, hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the present manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as recorded below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	10	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Description of original monument and accessories and/or subsequent restoration:

GLO 1886 SURVEY BY TODD-A/538
 TREE WAS 14" W.O. SET OAK POST IN REMAINS OF ORIG. TREE
 (NO WITNESSES) SURROUNDED W/STONES
 10" BLK. WAL. = N3°E 59 LKS
 12" LOCUST = S29°W 26 LKS

Description of corner evidence found and/or method applied in restoring or reestablishing corner:

DIG IN CONJUNCTION WITH MDOT SURVEYORS FOUND OLD RING OF STONES 18" DEEP. AN AXLE SHAFT WAS CENTERED IN THE CIRCLE OF STONES IN A MON. BOX JUST UNDER THE SURFACE. ANOTHER STONE WAS FOUND @ 24" DEPTH

NOTE: SEVERAL SURVEYS IN THE 1970'S USED A P.K. NAIL 7' EAST OF TRUE COR. FOUND. NONE OF THESE SURVEYS REVEALED MORE THAN "A P.K. NAIL FOUND" L.C.R.C. IN 3/35 IS OF THIS P.K.

Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET 5/8" BAR WITH STD. COUNTY CAP IN MON. BOX THRU CIRCLE OF STONES
 COR IS 2' EAST OF OLD FENCE TO NORTH PROJECTED. C-C OF M-216 & DELONG ROAD IS 1.5' N AND 10' E. OLD P.K. NAIL IS 7' EAST N&W 24" HIGH IN SE SIDE DBL. 48" OAK = N20°W 45.44'
 N&W 36" HIGH IN SE SIDE 12" ELM = S65°W 98.71'
 N&W 36" HIGH IN W SIDE 10" ELM = S20°E 96.68'
 N&W 60" HIGH IN SE SIDE 18" POPLAR = N50°E 64.7'

APPROVED BY PEER GROUP 7/12/93 AS PERPETUATION OF ORIGINAL CORNER

Surveyed by *Wayne A. Mostrom* Date JULY 16, 1993

Surveyor's Michigan License No. 14100

