

**SURVEY & REMONUMENTATION**

FILED

NOV 30 1993

004 PG 009

JUL 27 1 03 PM '93

COMMISSION

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

*Cynthia A. Smatt*  
REGISTER OF DEEDS  
ST. JOSEPH CO MICH

corners in  
ST. JOSEPH (County)  
FLOWERFIELD TWP.  
Public Land Survey  
Property Controlling in Section  
Miscellaneous  
Property in Sec.

Located In: T 5S R 12W  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_  
S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

Corner Code #  
I-7  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

Register of Deeds Stamp & File Number

Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
Private Claims \_\_\_\_\_

WAYNE A. MOSTROM, in a field survey on JUNE 9, 19 93, hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

Description of original monument and accessories and/or subsequent restoration:

1896 SURVEY IN A/730  
FOUND STONE  
10" BUTTERNUT = NW'LY 47 LKS  
10" BLK. WAL. = NW'LY 57 LKS  
186 SURVEY IN A/538  
STONE FROM ORIGINAL  
TREE STILL GREEN  
O. N67°E 1.61 CH.  
A.P. = N04°E 35.6'  
A.P. = S42°E 36.1'  
21" WAL. = N35°W 37.7'

L.C.R.C. 1/1 (1971)  
24" WAL. = N40°W 37.95'  
10" WAL. = N30°E 37.45'  
TELE. POLE = S45°W 41.70'  
RUSHLOW IN 1992  
FD. STONE IN MON. BOX  
12" WAL. = N45°E 37.1'  
TELE. RISER = N06°E 35'  
SE COR. HSE = N35°W 73.0'  
STO PILLAR = N45°W 74.0'

Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND STONE IN MON. BOX  
REMAINS OF WAL. STUMP = N35°W 37.6'  
HOUSE COR = N30°W 73.07'

Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET STD. CAP ON 5/8"X24" IRON BAR IN MON. BOX OVER STONE  
SE COR GAR. FTDN. = NORTH 142.90'  
SE COR HSE. FTDN. = N30°W 73.07'  
SW COR HSE. FTDN. = N40°W 86.37'  
NE COR. HSE. FTDN. = S30°W 109.98'  
COR. IS 1.6' SOUTH + 1.0' E. OF  $\text{\textcircled{C}}$  PAV'NT.



CORNER WAS APPROVED BY PEER GROUP 7/21/93 AS A PERPETUATION OF THE ORIGINAL CORNER.

Recorded by Wayne A. Mostrom  
Surveyor's Michigan License No. 14100

Date JULY 14, 1993