

**SURVEY & REMONUMENTATION**

NOV 30 1993

004 16 008

FILED

**COMMISSION**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

JUL 27 1 03 PM '93

corners in

ST. JOSEPH (County) Located In: Corner Code #/ #  
 FLOWERFIELD TWP. T 5S R 12W K-6  
 Public Land Survey T R  
 T R  
 T R  
 T R  
 Property Controlling S T R  
 in Section S T R  
 Miscellaneous S T R  
 Property in Sec. S T R

*Cynthia R. Lanatt*  
REGISTER OF DEEDS  
ST. JOSEPH CO MICH

Register of Deeds Stamp & File Number

Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 Private Claims \_\_\_\_\_

WAYNE A. MOSTROM, in a field survey on \_\_\_\_\_, 19 93, hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the present manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as recorded below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	13		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

**TE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

Description of original monument and accessories and/or subsequent restoration:

<u>GLO</u> 36" W.O.=S40°E 45 LKS 18" W.O.=N33°W 27 LKS 1972 BY SAYERS SHOWS MON BOX & PIPE 2663.71' S. & 2658.88' N OF COR'S TO N&S. ROAD COMMISSION-1960'S 1/2" PIPE OVER LARGE +1'D STONE 29" CHERRY=N7°W 193.9' 19" CHERRY=S14°W 90.93'	<u>1964 MDOT</u> PIPE OVER STONE IN BOX 29" CHERRY=N7°E 193.9' 19" CHERRY=S14°W 90.93' COR IS 2'E RDWY L.C.R.C.-3/32-1976 BAR IN MON BOX STAKE = S45°W 40' STAKE = S45°E 40' STAKE = N45°W 40'	<u>L.C.R.C.-1986 BY MDOT</u> ROD IN MON BOX 7" PINE = N50°E 62.9' SW COR HSE = N60°E 109.93' 7" PINE = N85°E 47' 7" PINE = S30°E 105.35' 1993 SURVEY BY HUNT-677/433 1/2" ROD IN MON BOX IN CL RDWY. 5/8" ROD = EAST 33' TEL. RISER = N30°E 51' & S20°E 99.9' SW COR HSE = N45°E 110.10'
---	---	--

Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND IRON BAR IN MON BOX OVER STONE 24" DEEP  
 SW COR HOUSE = N45°E 110.10'  
 IRON BAR = EAST 33'  
 C ROAD = EAST 1.7'  
 CHECKED TO TELE. RISERS ON 1993 SURVEY O.K.  
 NOTE: ROAD AS BEEN IMPROVED - ALL OLD TREES WERE REMOVED

Description of monument for corner and accessories established to perpetuate locating the position of the corner:

WEST 1/4 COR SEC. 13  
 SET 5/8"X24" BAR W/STD. CAP OVER LARGE STONE IN MON BOX  
 IRON ROD = EAST 33.02'  
 NW COR GARAGE FTDN = N40°E 154.70'  
 SW COR HSE FTDN = N45°E 110.10'  
 C RDWY = EAST 1.7'  
 C TELE. RISER = N30°E 51.30'  
 C TELE. RISER = S20°E 99.9'



Recorded by *Wayne A. Mostrom*

Date JULY 15, 1993

Surveyor's Michigan License No. 14100