

JAN 24 1996

004 PG 016

FILED

DEC 7 10 47 AM '93

COMMISSION LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

Cynthia R. Lanett  
REGISTER OF DEEDS  
ST. JOSEPH COUNTY

For corners in

ST. JOSEPH  
(County)

Located In:

Corner Code #:

FLOWERFIELD TWP.

- 1. Public Land Survey T 5S R 12W L-5
- T \_\_\_\_\_ R \_\_\_\_\_
- T \_\_\_\_\_ R \_\_\_\_\_
- T \_\_\_\_\_ R \_\_\_\_\_
- 2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

Register of Deeds Stamp & File Number

I, WAYNE A. MOSTROM in a field survey on SEPTEMBER 13, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

L-5

GLO

20" W.O. = N21/2°W 169 LKS BOOK A, PAGE 660 (1892)  
 11" B.O. = S72°W 78 LKS BOOK A, PAGE 665 (1892)  
 ROAD COMMISSION-1960'S SET STAKE & OVER IT A STONE  
 15" CHERRY = N59°E 118.13' 16" BLK. L. = S66°E 1.91CH  
 12" BLK. O. = N73°E 86.22' "NO TRACE OF ORIGL COR. WITT.  
 27" BLK. O. = S47°E 60.95' COULD BE FOUND"

MOSTROM SURVEY OF &  
 LCRC IN L-1, P. 139  
 OLD STONE WAS PLOWED  
 OUT RESET USING 18"  
 IRON PIPE  
 6" OAK = WEST 45.35'  
 NW HSE. COR. = SW 46.56'  
 CONC. MON. @ RD. R/W =  
 E. 39.89'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-5

FOUND CAPPED 1" PIPE 26" LONG IN CLAY TILE  
 CONC. MON. = E. 39.89'  
 HSE COR = SW 46.36  
 OAK = WEST 45.35'  
 CORNER AGREES W/PLAT OF PINEVIEW GST.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-5

(1/4 COR. BET. SEC. R&13)

SET 5/8" X 24" IRON BAR & STD. CAP  
 SE COR GAR = S0°W 108.06'  
 NW COR HSE = S40°W 71.66'  
 NE COR HSE = S20°W 46.36'  
 CONC. MON. @ RD. R/W = E. 39.8'  
 N & W IN N. SIDE 12" OAK = N85°W 45.35'

APPROVED BY PEER GROUP  
AS BEST AVAILABLE EVIDENCE  
OF CORNER



Signed by Wayne A. Mostrom  
 Surveyor's Michigan License No. 14100

Date 11/11/93