

NOV 15 1994

LIBER 4 PAGE 56

**COMMISSION LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>ST. JOSEPH</u> (County)	Located In:	Corner Code <del>##</del>
COLON TWP.		
1. Public Land Survey	T <u>6</u> S R <u>9</u> W	<u>A-3</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

STATE OF MICHIGAN  
 ST. JOSEPH COUNTY  
 FILED

18 OCT 94 2:30 P.M.

CYNTHIA JARRATT  
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, DAVID W. MOSTROM, in a field survey on OCTOBER 3, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

(A-3) SW CORNER SEC. 6, T6S, R9W  
 NO EVIDENCE OF GLO WITNESSES  
1866 SURVEY - BOOK A, PG. 144  
 STONE FROM OLD BRG. TREE  
 NO WITNESSES

1961 - MDOT  
 LARGE PT. STONE W/IRON  
 RD. SIGN POST = N30°E 41.56'  
 7" OAK = N70°E 83.33'  
 RR ANCHOR POST = S30°W 67.08'  
 NOTTAWA TWP. COR. = SOUTH  
 60.72'  
 CONST.  $\odot$  = W. 37.7'

LCRC - BOOK 2, PG. 270  
 1" PIPE IN MON. BOX  
 IRON BAR = N10°W 47.25'  
 IRON BAR = N70°E 34.47'  
 IRON BAR = S10°W 61.20'  
 PINCH PIPE = S75°E 35.37'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(A-3)  
 FOUND BOAT SPIKE IN MON. BOX (NOTHING UNDER BOAT SPIKE)  
 $\odot$  HWY = WEST 38'±  
 IRON BAR = N10°W 47.25'  
 IRON BAR = N70°E 34.47'  
 IRON BAR = S10°W 61.20'  
 PINCH PIPE = S75°E 35.37'  
 NOTTAWA TWP. COR. = SOUTH 60.72'

RATIFIED BY PEER GROUP  
 IN ACCORDANCE WITH P.A. 345  
 ON OCT. 10, 1994  
CO. REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(A-3) SW COR. SEC. 6, T6S, R9W  
 SET 5/8" X 24" IRON BAR W/STD. CAP  
 P. POLE = N85°W 94.10'  
 1/2" IRON BAR = N10°W 47.25'  
 1/2" IRON BAR = N70°E 34.47'  
 1/2" IRON BAR = S10°W 61.20'  
 IRON ANCHOR = N77°E 146.67'  
 NOTTAWA TWP. COR. = SOUTH 60.72'

CORNER FALLS IN  $\odot$  OF  
 ROAD TO EAST  
 HWY.  $\odot$  = WEST 38'

NOTE: THE LOCATION OF  
 THIS CORNER IN RELATIONSHIP  
 TO THE TOWNSHIP LINE WAS  
 NOT VERIFIED.



Signed by J. W. Mostrom

Date OCTOBER 12, 1994

Surveyor's Michigan License No. 32339