

# SURVEY & REMONUMENTATION

APR 10 1995

LIBER 4 PAGE 69

## LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in **COMMISSION**

<u>ST. JOSEPH</u> (County)	Located In:	Corner Code #
COLON TOWNSHIP		
1. Public Land Survey	T <u>6S</u> R <u>9W</u>	<u>A-4</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

STATE OF MICHIGAN  
ST. JOSEPH COUNTY  
FILED

6 DEC 94 4:30 P.M.

CYNTHIA JARRATT  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	A
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, DAVID W. MOSTROM, in a field survey on OCTOBER 5, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

(A-4) WEST 1/4 CORNER SECTION 7

NO GLO CORNER SET

1866 - BOOK A, PG. 144

STAKE BETWEEN NW & SW COR'S

NO WITNESSES

1961- MDOT

FOUND LARGE POINTED STONE - RAISED WITH 1" PIPE

RR RAIL FENCE POST = N90°E 27.45'

RR RAIL FENCE POST = S25°W 74.15'

NOTTAWA TWP. COR. = SOUTH 66.55'

CORNER IS 7.43'E. OF CONST. CL

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(A-4)

FOUND BOAT SPIKE IN MON. BOX IN PROJ.

OF FENCE LINE TO EAST

NOTTAWA TWP. COR. = SOUTHERLY 66.64'

EXISTING HWY. CENTERLINE = WEST 8'

RATIFIED BY PEER GROUP  
IN ACCORDANCE WITH P.A. 345  
ON Nov. 14, 1994  
Willis CO. REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(A-4) WEST 1/4 CORNER SECTION 7

SET 5/8" X 24" IRON WITH STD. CAP IN PLACE OF BOAT SPIKE IN MON. BOX

PK NAIL & TAG IN TOP OF R.R. TIE POST = N30°W 122.64'

PK NAIL & TAG 5' HIGH ON S. SIDE OF P. POLE = S54°W 99.00'

EXISTING HWY. CENTERLINE = WEST 8'

CONC. ROW MARKER = EAST 52.16'

PAINT + ON TOP OF RR ANCHOR RAIL = EAST 52.90'

NOTTAWA TWP. COR. = SOUTHERLY 66.64'

CORNER IS 4.4' ± E. OF TWP. LINE PER MDOT RECORDS



Signed by J. W. Mostrom

Date NOV. 21, 1994

Surveyor's Michigan License No. 32339