

NOV 15 1994

LAND CORNER RECORDATION CERTIFICATE

LIBER 4 PAGE 57

Filing Requirement of Act 74, Mich. P.A. 1970

COMMISSION

For corners in

ST. JOSEPH (County)	Located In:	Corner Code #:
COLON TWP.		
1. Public Land Survey	T 6S R 9W	A-5
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

STATE OF MICHIGAN
ST. JOSEPH COUNTY
RECORDED

18 OCT 94 2:30 P.M.

CYNTHIA JARRATT
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, DAVID W. MOSTROM, in a field survey on OCTOBER 5, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered; found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(A-5) SW CORNER SEC. 7 T6S, R9W

NO EVIDENCE OF GLO WITNESSES
GLO JOG = 1.10 CHAINS

1865 SURVEY - BOOK A, PG. 124

STONE FROM ORIG. BRG TREES
NO WITNESSES

1866 SURVEY - BOOK A, PG 144

STONE FROM ORIG. BRG TREES
NO WITNESSES

1961 - MDOT

LARGE PT. STONE WITH IRON
RR ANCHOR POST = N35°E 44.58'
21" WALNUT = N70°E 56.50'
23" WALNUT = S45°E 46.48'
NOTTAWA TWP COR = SOUTH 74.25'
CL HWY = WEST 6.67'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(A-5)

FOUND BOAT SPIKE IN MON. BOX (NOTHING FOUND UNDER BOAT SPIKE)
NOTTAWA TWP. COR. = SOUTH 74.25'
CL HWY = WEST 7'

RATIFIED BY PEER GROUP
IN ACCORDANCE WITH P.A. 345
ON OCT. 10, 1994
Wagon CO. REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(A-5) SW CORNER SEC. 7 T6S, R9W

SET 5/8" X 24" IRON BAR W/STD. CAP IN MON. BOX
SE HOUSE COR. = N77°W 170.08'
IRON ANACHOR POST = N77°E 131.15'
NW HOUSE COR. = S58°E 133.38'
SW HOUSE COR. = S42°E 162.74'
NOTTAWA TWP. COR. = SOUTH 74.25'
CL HWY = WEST 7'
CORNER FALLS IN PROJ. OF ROAD TO EAST

NOTE: THE LOCATION
OF THIS CORNER IN
RELATIONSHIP TO THE
TOWNSHIP LINE WAS NOT
VERIFIED.



Signed by J. D. W. Mostrom Date OCTOBER 12, 1994

Surveyor's Michigan License No. 32339