

**SURVEY &
REMONUMENTATION**

JAN 17 1996 LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
ST. JOSEPH
(County)

COMMISSION Located In:

Corner Code #

LIBER **4** PAGE **142**

COLON TWP.

- | | | | | | | |
|--------------------------------------|---|-----------|---|-----------|------------|-------|
| 1. Public Land Survey | T | <u>6S</u> | R | <u>9W</u> | <u>A-7</u> | |
| | T | _____ | R | _____ | _____ | |
| | T | _____ | R | _____ | _____ | |
| | T | _____ | R | _____ | _____ | |
| 2. Property Controlling in Section | S | _____ | T | _____ | R | _____ |
| | S | _____ | T | _____ | R | _____ |
| 3. Miscellaneous Property in Section | S | _____ | T | _____ | R | _____ |
| | S | _____ | T | _____ | R | _____ |

STATE OF MICHIGAN
ST. JOSEPH COUNTY
FILED

11 MAY 95 4:23 P.M.

CYNTHIA JARRATT
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						

I, DAVID W. MOSTROM, in a field survey on JANUARY 3, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(A-7) SW COR. SEC. 18, COLON TWP.

GLO
NOTTAWA TWP. COR. = SOUTH 61.38'
1865 SURVEY IN BOOK A, PG. 124
STONE FROM ORIG. BRG. TREE
NO WITNESSES

1961 MDOT
FOUND PK AND CAP SET BY OTHERS
19" OAK = N20°E 75.47'
A. POST = EAST 39.60'
A. POST = S45°W 75.88'
NOTTAWA TWP. COR. = SOUTH 72.75'

1985 MDOT
SURVEY CENTERLINE = WEST 2.87'
NOTTAWA TWP. COR. = SOUTH 72.75'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(A-7)

FOUND 1" PIPE IN MON. BOX
NOTTAWA TWP. COR. = SOUTH 72.79'
24" OAK = N30°E 75.47'
A. POST (LEANING) = EAST 39.60'
EXISTING HWY. CENTERLINE = WEST 3'±

RATIFIED BY PEER GROUP
IN ACCORDANCE WITH P.A. 345
ON MAY 8th, 19 95
W. Green CO. REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(A-7) SW COR. SEC. 18, COLON TWP.

SET 5/8" X 24" IRON BAR W/STD. CAP IN 1" PIPE IN MON. BOX
CORNER FALLS IN PROJ. OF FENCE TO EAST
NOTTAWA TWP. COR. = SOUTH 72.79'
CONC. R/W MARKER = EAST 56.75'
N & W 5' HIGH ON NW. SIDE OF 24" OAK = N30°E 75.47'
N & W 6' HIGH ON S. SIDE OF 18" OAK = N70°E 72.60'
N & W 6' HIGH ON NE. SIDE OF 10" OAK = S60°E 55.96'



LIBER 4 PAGE 142

Signed by J. W. Mostrom

Date MAY 9, 1995

Surveyor's Michigan License No. 32339

30th 10 95

REMONUMENTATION