

**SURVEY &
MONUMENTATION**

JAN 17 1996

COMMISSION LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in ST. JOSEPH Located In: _____ Corner Code # _____
(County)
COLON TWP.

1. Public Land Survey	T	<u>6S</u>	R	<u>9W</u>	<u>A-9</u>	
	T	_____	R	_____	_____	
	T	_____	R	_____	_____	
	T	_____	R	_____	_____	
2. Property Controlling in Section	S	_____	T	_____	R	_____
	S	_____	T	_____	R	_____
3. Miscellaneous Property in Section	S	_____	T	_____	R	_____
	S	_____	T	_____	R	_____

LIBER **4** PAGE **138**

STATE OF MICHIGAN
STATE OF MICHIGAN
ST. JOSEPH COUNTY
FILED

11 MAY 95 4:17 P.M.

CYNTHIA JARRATT
REGISTER OF DEEDS
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, DAVID W. MOSTROM, in a field survey on APRIL 7, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1					
3											
4	7	8	9	10	11	12					
5											
6	18	17	16	15	14	13					
7											
8	19	20	21	22	23	24					
9											
10	30	29	28	27	26	25					
11											
12	31	32	33	34	35	36					
13											

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(A-9) SW COR. SEC. 19, COLON TWP.

GLO
NOTTAWA TWP. COR. = SOUTH 19.14'
1865 SURVEY IN BOOK A, PG. 126
STAKE FROM ORIG. BRG. TREES
NO WITNESSES

1960 MDOT
CORNER NOT LABELED
HWY. CENTERLINE = EAST 2.05'
NOTTAWA TWP. COR. = SOUTH 19.11'
FENCE POST = N73°E 36.42'
R.R. IRON = S89°E 30.47'
STUMP = S48°E 46.17'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(A-9)

FOUND MON. BOX IN APPROX. LOCATION OF CORNER
THERE WAS NO IRON IN MON. BOX
HWY. CENTERLINE = EAST 2'±
SET 5/8" X 24" IRON BAR W/STD. CAP 19.11' NORTH OF NOTTAWA TWP.
CORNER AND ON LINE BETWEEN SE COR. SEC. 24 AND EAST 1/4 COR.
SEC. 24 NOTTAWA TWP.

RATIFIED BY PEER GROUP
IN ACCORDANCE WITH P.A. 345
ON MAY 8th, 1995
Willis CO. REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(A-9) SW COR. SEC. 19, COLON TWP.

5/8" X 24" IRON BAR W/STD. CAP IN MON. BOX
EXISTING HWY. CENTERLINE = EAST 1.8'±
NOTTAWA TWP. COR. = SOUTH 19.11'
CORNER IS 1.0' NORTH OF FENCELINE PROJ. TO EAST
N & W 2.0' HIGH IN S. SIDE OF P. POLE = S84°E 53.58'
N & W 2.0' HIGH IN N. SIDE OF P. POLE = S78°W 61.78'
N & W 2.0' HIGH IN N. SIDE OF ANCHOR POST = S75°W 61.10'
N & W 2.0' HIGH IN S. SIDE OF FENCE POST = S55°W 74.90'



Signed by [Signature]

Date MAY 10, 1995

Surveyor's Michigan License No. 32339

REMONUMENTATION

LIBER 4 PAGE 100