

JAN 24 1996

004 PG 019

COMMISSION LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

ST. JOSEPH (County)	Located In:	Corner Code -#
COLON TWP.	T 6S R 9W	C-2
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

FILED

DEC 7 10 48 AM '93

Cynthia L. Lamott
REGISTER OF DEEDS
ST. JOSEPH COUNTY

Register of Deeds Stamp & File Number

I, WAYNE A. MOSTROM, in a field survey on OCT. 11, 19 93
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned
in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the
current manual of survey instructions of the United States Department of the Interior, Bureau of Land
Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5
above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a
Court of Law; established, re-established, monumented, re-monumented, recovered, found as
expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded
on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

<u>1906 SURVEY BY REED IN</u> <u>BOOK B, PAGE 276</u>	<u>ROAD COMM - 1963</u>	<u>LCRC IN 1/59 & 1974 SURVEY</u>
POINTED STONE	POINTED STONE & METAL	FD 3/4" PIPE
6" MAPLE = S11 1/4°E .46 1/8 CH	SE COR BDDG = N24°W 115'	24" MAPLE = SE 30.79'
16" MAPLE = S57°W .85 1/2 CH	NW COR HSE = S36°W 63.5'	NW COR HSE = SW 63.5'
	32" MAPLE = S59°W 56.85'	SIDEWALK = SW 11.2'
	24" MAPLE = S11°E 30.6'	36" MAPLE = SW 55.4'
	CL RDWY = N 20.8'	

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

DEPRESSION IN YARD WHERE OLD TREE ONCE STOOD = S59°W 56.85' & S11°E 30.6'
SIDEWALK = SW 11.2'
NW COR HSE = SW 63.5'
FD 3/4" PIPE 26" LONG IN C DITCH ON S SIDE RDWY

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

WEST 1/4 COR SEC. 5
SET 5/8" X 24" IRON BAR & STD. CAP.
NW COR. HSE. = S36°W 63.5'
NE COR. HSE. = S20°E 53.71'
CL RDWY = N. 22.8' (REALIGNED RDWY)
N&W IN NE SIDE BRACE POLE = N40°W 75.41'
N&W IN N SIDE 30" MAPLE = S40°W 39.5'

APPROVED BY PEER GROUP
AS RE-ESTABLISHMENT OF
ORIGINAL CORNER



Signed by *Wayne A. Mostrom*

Date OCTOBER 12, 1993

Surveyor's Michigan License No. 14100