

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 4 PAGE 237

For corners in

ST. JOSEPH
(County)
COLON TWP.

Located in:

Corner Code #

STATE OF MICHIGAN
ST. JOSEPH COUNTY
FILED

6 AUG 96 3:43 P.M.

CYNTHIA JARRATT
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

- | | | | | | | | |
|--------------------------------------|---|----------|---|---|----------|---|------------|
| 1. Public Land Survey | T | <u>6</u> | S | R | <u>9</u> | W | <u>C-4</u> |
| | T | | R | | | | |
| | T | | R | | | | |
| | T | | R | | | | |
| 2. Property Controlling in Section | S | | T | | R | | |
| | S | | T | | R | | |
| 3. Miscellaneous Property in Section | S | | T | | R | | |
| | S | | T | | R | | |
4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2			
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

I, DAVID W. MOSTROM, in a field survey on APRIL 8, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(C-4) $\frac{1}{4}$ CORNER COMMON TO SECTIONS 7 & 8 T6S, R9W

GLO 1974 LCRC IN BK 3, PG 42 &
1974 MOSTROM SURVEY

13" W. OAK = S02°W 148.5'
14" B. OAK = N54 $\frac{1}{2}$ °W 31.02'

1866 SURVEY IN BK A, PG 144

FOUND POINTED STONE
24" OAK = SOUTH 22.5'
10" HICKORY = NORTH 22.75'

STAKE FROM ORIG. BEARINGS,
NOW GREEN

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(C-4)

FOUND 8" X 18" X 20" LONG POINTED STONE
POINT OF STONE FALLS 1.2' WEST OF A 15" X 20" CONC. ANCHOR POST
STONE FALLS IN LINE WITH FENCE TO EAST AND
IN REMAINS OF NORTH-SOUTH FENCE

**SURVEY &
REMONUMENTATION**

OCT 03 1996

COMMISSION

RATIFIED BY PEER GROUP
IN ACCORDANCE WITH P.A. 345
ON May 13, 1996
Wm CO. REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(C-4)

SET 5/8" X 24 IRON BAR W/STD. CAP (MOVED STONE ASIDE)
NW COR. CONC. ANCHOR POST = EAST 1.20'
 $\frac{1}{2}$ " IRON BAR (1.5' DEEP) = N45°E 38.29'
 $\frac{1}{2}$ " IRON BAR (1.5' DEEP) = S45°E 42.13'
N & W 4.5' HIGH IN N. SIDE OF 18" MAPLE = EAST 11.01'
N & W 3.4' HIGH IN S. SIDE OF 48" MAPLE = S06°E 27.29'
N & W 3.0' HIGH IN E. SIDE OF 48" OAK = N04°W 76.17'



Signed by J. W. Mostrom Date JULY 26, 1996

Surveyor's Michigan License No. 32339

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983

REMONUMENTATION