

# SURVEY & REMONUMENTATION

APR 07 1998

## SECTION

## LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 5 PAGE 38

For corners in

ST. JOSEPH  
(County)

Located In:

Corner Code #

COLON TWP.  
1. Public Land Survey

T	6S	R	9W	C-5
T		R		
T		R		
T		R		
S		T	R	
S		T	R	
S		T	R	
S		T	R	

2. Property Controlling in Section  
3. Miscellaneous Property in Sec.

STATE OF MICHIGAN  
ST. JOSEPH COUNTY  
FILED

14 NOV 97 8:18 A.H.

CYNTHIA JARRATT  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, WAYNE A. MOSTROM, in a field survey on NOV. 6, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	5	6	7	8	9	10	11	12	13	14	15	16
3												
4	7	8	9	10	11	12	13	14	15	16	17	18
5												
6	10	11	12	13	14	15	16	17	18	19	20	21
7												
8	13	14	15	16	17	18	19	20	21	22	23	24
9												
10	16	17	18	19	20	21	22	23	24	25	26	27
11												
12	19	20	21	22	23	24	25	26	27	28	29	30
13												
14	22	23	24	25	26	27	28	29	30	31	32	33
15												
16	25	26	27	28	29	30	31	32	33	34	35	36
17												
18	28	29	30	31	32	33	34	35	36	37	38	39
19												
20	31	32	33	34	35	36	37	38	39	40	41	42
21												
22	34	35	36	37	38	39	40	41	42	43	44	45
23												

### A. Description of original monument and accessories and/or subsequent restoration:

1865 SURVEY IN A/125	MDOT 1942	MDOT	LCRC IN 3/42 (1974)
STONE FROM ORIG. BRG'S	1/2" PIPE DRIVEN THRU REMAINS OF STK. IN MON. BOX	24" WILLOW=S46°E 42.31' 5" OAK=S63°W 55.03' 10" APPLE=N48°W 68.72'	STONE IN MON. BOX 10" COR. POST=SW 38.7' 18" MAPLE=SE 65.4' 10" HEDGE POST=N. 29.4'
1866 SURVEY IN A/144	17" WAL.=S14°W 99.08' 11" OAK=N85°W 150.57' 12" CHERRY=N57°W 44.75' 31" OAK=N86°E 174.35'		1976 SURVEY BY SAYERS SAME DATA AS LCRC

### B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND +1'D. STONE IN MON. BOX  
18" MAPLE = SE 65.4'  
10" HEDGE POST = NORTH 29.4'  
COR. IS IN @ RDWY TO EAST & SOUTH

RATIFIED BY PEER GROUP  
IN ACCORDANCE WITH P.A. 345  
ON NOV. 10, 1997  
Wayne CO. REPRESENTATIVE

### C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET 5/8" X 9" BAR W/STD. CAP OVER T'D  
STONE IN MON. BOX  
NW COR HSE=S50°E 94.20'  
N & W IN N. SIDE 12" TREE=S80°E 65.20'  
N & W IN SE SIDE 30" OAK=N20°E 41.44'  
SE COR. HOUSE=N30°E 141.75'



Signed by Wayne A. Mostrom  
Surveyor's Michigan License No. 14100

Date NOVEMBER 11, 1997

# REMONUMENTATION

LIBER 5 PAGE 38

38