

SURVEY & REMONUMENTATION

MAY 05 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 4 PAGE 96

For corners in

<u>ST. JOSEPH COUNTY</u> (County)	Located In:	Corner Code #
COLON TOWNSHIP		
1. Public Land Survey	T <u>6S</u> R <u>9W</u>	<u>C-8</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

STATE OF MICHIGAN
ST. JOSEPH COUNTY
FILED

19 JAN 95 10:54 A.M.

CYNTHIA JARRATT
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, DAVID W. MOSTROM, in a field survey on DECEMBER 28, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(C-8) 1/4 CORNER COMMON TO SECTIONS 19 & 20

1865 SURVEY IN BK. A, PG. 127
+STONE FROM ONE OLD BRG TREE
6" SUGAR = N86 3/4°E 51 LINKS
14" HICKORY = S39°E 44 LINKS

1960'S ROAD COMMISSION
LARGE +'D STONE IN MON. BOX
SW COR HOUSE = N37°E 136.60'
A. POST = NW 56.8'
A. POST = SW 47.8'
A. POST = SE 32.05'

1981 SURVEY BY MOSTROM
FOUND STONE IN MON. BOX
A. POST = N36°W 57'
A. POST = S52°W 48.5'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(C-8)

FOUND +'D STONE IN MON. BOX
SW. COR. HOUSE = N37°E 136.60'
A. POST = NW 56.8'
A. POST = SW 47.8'

RATIFIED BY PEER GROUP
IN ACCORDANCE WITH P.A. 345
ON JAN. 9, 19 95
W. M. M. CO. REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(C-8) 1/4 CORNER COMMON TO SECTIONS 19 & 20

SET 5/8" IRON BAR W/STD. CAP IN CONC. OVER STONE
SE. HSE. CORNER = N53°E 158.18'
N & W 2.0' HIGH ON N. SIDE OF P. POLE = S78°W 131.47'
N & W 2.0' HIGH ON S. SIDE OF 34" HICKORY = N82°W 197.94'
N & W 2.0' HIGH ON NE SIDE OF P. POLE = N12°W 161.37'
CORNER FALLS IN CL OF N-S GRAVEL ROAD
PROJ. OF GRAVEL ROAD TO WEST = SOUTH 2'



Signed by J. W. M. Date JANUARY 12, 1995

Surveyor's Michigan License No. 32339

th 10 1995

REMONUMENTATION

LIBER 4 PAGE 96