

**SURVEY & REMONUMENTATION**

**LAND CORNER RECORDATION CERTIFICATE**

For corners in APR 10 1995

Filing Requirement of Act 74, Mich. P.A. 1970 LIBER **4** PAGE **98**

ST. JOSEPH  
(County) **COMMISSION** Located In: \_\_\_\_\_ Corner Code 1-5  
COLON TWP.

1. Public Land Survey	T	<u>6S</u>	R	<u>9W</u>	<u>1-5</u>
	T	_____	R	_____	_____
	T	_____	R	_____	_____
	T	_____	R	_____	_____
2. Property Controlling in Section	S	_____	T	_____	R
	S	_____	T	_____	R
3. Miscellaneous Property in Sec.	S	_____	T	_____	R
	S	_____	T	_____	R

STATE OF MICHIGAN  
ST. JOSEPH COUNTY  
FILED

23 JAN 95 9:21 A.M.

CYNTHIA JARRATT  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	16	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, DAVID W. MOSTROM in a field survey on NOVEMBER 29, 19 94 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

(I-5) CORNER COMMON TO SECTIONS 10, 11, 14, 15

1862 SURVEY BY N.S. ANDREWS

STONE SET FROM OLD WIT. STUMP

1903 & 1904 SURVEYS IN BOOK B, PG 104 & BOOK 1, PG. 77 & BOOK 1, PG 99

+ STONE

2 WITNESSES OUT

1933 SURVEY IN BK B, PG. 550

+ STONE

2 WITNESSES OUT

MDOT (NO DATE)

FD. + STONE - RAISED W/5/8"

IRON & BOX

NE HSE COR = S30°E 105.72'

NW HSE COR = S18°E 88.85'

HWY CL = NORTH 6.85'

1974 LCRC IN BK 1, PG 97

& 1974 SAYERS SURVEY

PIPE IN MON. BOX

MAILBOX = NE 55'

CL HWY = NORTH 6.8'

1992 LCRC IN BK 3, P-229

FD 5/8" REBAR IN MON BOX

6.8' S. OF HWY CL

PP = N01°E 39.08'

TELE. RISER BOX = N63°E

107.40

TELE. RISER BOX = S25°W

41.03'

N. LEG SIGN POST = S80°W

78.25'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(I-5)

FOUND 5/8" REBAR IN MON. BOX 6.8' SOUTH OF HWY. CL

MAIL BOX = NE 55'

4 WITNESSES FROM 1992 L.C.R.C. CHECK OK

RATIFIED BY PEER GROUP  
IN ACCORDANCE WITH P.A. 345  
ON Dec. 12, 1994  
Warr CO. REPRESENTATIVE



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(I-5) CORNER COMMON TO SECTIONS 10, 11, 14, 15

SET 5/8" X 24" IRON BAR/STD. CAP IN MON. BOX 6.8' SOUTH OF HWY. CL

N & W 2' HIGH ON W. SIDE OF PP. = N05°W 39.09'

N & W 2' HIGH ON NE SIDE OF PP. = S60°E 106.70'

NE HSE CORNER (FOUNDATION) = S30°E 105.72'

NW HSE CORNER (FOUNDATION) = S18°E 88.85'

LIBER 4 PAGE 98

Signed by J.W. Mostrom

Date DECEMBER 14, 1994

Surveyor's Michigan License No. 32339

**REMONUMENTATION**