

LAND CORNER RECORDATION CERTIFICATE  
 Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 6 PAGE 36

STATE OF MICHIGAN  
 ST. JOSEPH COUNTY  
 FILED

For corners in Nottawa Township

St. Joseph County Located In: Corner Code #  
 (County)

1. Public Land Survey T 6 S R 10 W C-6  
 T R  
 T R  
 T R  
 2. Property Controlling S T R SURVEY &  
 in Section S T R REMONUMENTATION  
 3. Miscellaneous S T R  
 Property in Sec. S T R

1 MAY 2000 9:37:51 AM

CYNTHIA L. JARRATT  
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_ SECTION \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18	⊙	17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, David W. Mostrom, in a field survey on March 30, 2000, do state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

(C-6) 1/4 CORNER COMMON TO SECTIONS 17 & 18, NOTTAWA TOWNSHIP

A. Description of original monument and accessories and/or subsequent restoration:

GLO 1974 Mostrom Survey  
 10" Hickory = N22°E 16.5' Survey along East line of Section uses  
 8" Burr Oak = S70°W 18.48' NE Corner Section 18 & SE Corner  
 Section 18 for line

1960's Road Commission 1983 Mostrom Survey  
 Index shows this corner was dug Uses split of mile between section corners  
 for with a motor grader & not found to establish section breakdown

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No corner exists in field  
 Location of split between section corner falls in the centerline  
 of Angevine Road and in line with the old fenceline running  
 East, East of Angling Road.  
 Set 5/8" x 24" Iron Bar with Standard Cap in Monument Box at this location



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

5/8" x 24" Iron Bar with standard cap in Monument Box  
 N & W 2.0' High in W. Side of 10" Maple = N30°E 86.82'  
 N & W 2.0' High in SW Side of P. Pole = N40°W 45.20'  
 N & W High in S. Side of 14" Mulberry = West 32.55'  
 N & W 2.0' High in NW Side of 12" Oak = S30°W 84.78'

RATIFIED BY PEER GROUP  
 IN ACCORDANCE WITH P.A. 345  
 ON April 10, 2000  
 Waus CO. REPRESENTATIVE

Signed by J. D. W. Mostrom David W. Mostrom Date April 19, 2000  
 Surveyor's Michigan License No. 32339

REMONUMENTATION

LIBER 6 PAGE 36