

**SURVEY &  
REMONUMENTATION**

**JAN 17 1996 LAND CORNER RECORDATION CERTIFICATE**

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

**COMMISSION**

LIBER **4** PAGE **186**

ST. JOSEPH Located In:

Corner Code #

STATE OF MICHIGAN  
ST. JOSEPH COUNTY  
FILED

24 OCT 95 10:35 A.M.

CYNTHIA JARRATT  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

NOTTAWA TWP.			
1. Public Land Survey	T	<u>6 S</u> R <u>10 W</u>	<u>C-10</u>
	T	_____ R _____	_____
	T	_____ R _____	_____
	T	_____ R _____	_____
2. Property Controlling in Section	S	_____ T _____ R _____	_____
	S	_____ T _____ R _____	_____
3. Miscellaneous Property in Section	S	_____ T _____ R _____	_____
	S	_____ T _____ R _____	_____

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2							
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, WAYNE A. MOSTROM, in a field survey on SEPTEMBER 25, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

<u>1865 SURVEY IN BK A, P 93</u>	<u>1972 SURVEY BY DON PIERCE</u>	<u>1989 SURVEY BY MOSTROM</u>
SURVEY SHOWS COR. ON $\frac{1}{2}$ OF HWY. TO THE NW	FD. $\frac{1}{2}$ " PIPE IN MON. BOX IN FENCELINE TO WEST PK NAIL = N0°05'28"W 97.57'	FD. 3/4" PIPE IN MON. BOX IN $\frac{1}{2}$ N-S RDWY & $\frac{1}{2}$ HWY. TO NW L.C.R.C. IN L-4, P-167 (1995)
<u>SAYERS 1979 SURVEY</u>	<u>1977 SURVEY BY DOUG PIERCE</u>	P.P. N01°W 134.97
SHOWS "IRON IN MONUMENT BOX"	FD. $\frac{1}{2}$ " PIPE IN MON. BOX	U.P. N41°W 86.22'
		10" WALNUT N84°W 52.31'
		P.P. N89°E 31.69'

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

FD. 3/4" X 12" LONG PIPE OVER +1D STONE IN MON. BOX CORNER IS IN  $\frac{1}{2}$  HWY. TO NW, IN FENCELINE TO WEST & IN  $\frac{1}{2}$  N-S RDWY ABOVE REFERENCES FROM L.C.R.C. IN 4/167 ARE IN PLACE

RATIFIED BY PEER GROUP  
IN ACCORDANCE WITH P.A. 345  
ON Oct. 23, 1995  
Wayne CO. REPRESENTATIVE

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

SET 5/8" X 13" LONG IRON BAR IN CONC. IN MON. BOX  
N & W IN N. SIDE OF P.P. = EAST 31.81'  
N & W IN N. SIDE OF 8" WAL. = S86°W 38.35'  
N & W NE SIDE OF 30" HICK. = N56°W 117.84'  
N & W NE SIDE OF BRACE POLE = N41°W 86.21'  
COR. IS IN CL N-S RDWY & PROJ. OF CC OF M-86 TO NW & TO EAST



Signed by Wayne A. Mostrom Date OCTOBER 24, 1995  
Surveyor's Michigan License No. 14100

**REMONUMENTATION**

LIBER **4** PAGE **186**