

**SURVEY &
REMONUMENTATION**

MAY 07 1997

**LAND CORNER RECORDATION CERTIFICATE
COMMISSION Filing Requirement of Act 74, Mich. P.A. 1970**

LIBER **4** PAGE **271**

For corners in
ST. JOSEPH
(County)

Located In:

Corner Code #

NOTTAWA TWP.

1. Public Land Survey	T	<u>6S</u>	R	<u>10W</u>	<u>E-9</u>
	T	_____	R	_____	_____
	T	_____	R	_____	_____
	T	_____	R	_____	_____
2. Property Controlling in Section	S	_____	T	_____	_____
	S	_____	T	_____	_____
3. Miscellaneous	S	_____	T	_____	_____
Property in Section	S	_____	T	_____	_____

STATE OF MICHIGAN
ST. JOSEPH COUNTY
FILED

5 DEC 96 12:34 P.M.

CYNTHIA JARRATT
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, WAYNE A. MOSTROM, in a field survey on NOVEMBER 14, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	16	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

<u>1908 SURVEY IN B/414</u> SHOWS "STONE"	<u>1973 LCRC (1/25) & SURVEY (374/534)</u> BY J. CLAPP	<u>1976 SURVEY & LCRC</u> IN 1976 BY MOSTROM
<u>SAYERS 1977 SURVEY</u>	SET "T" IRON #14091 P.P. = NW 50.57' P.P. = ENE 80.26'	FOUND "T" IRON GUY POLE = ESE 80.51' P.P. = NW 50.7' P.P. = ENE 80.26'
<u>SAME WITT. AS LCRC</u> IN L-1, P-25.	GUY POLE = ESE 80.51'	
<u>1982 SURVEY BY MOSTROM: FD. "T" IRON; A.P. = N45°W 46.76'; A.P. = N45°E 48.2'; COR. IS IN CL</u>		

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner: INTERSEC. OF RDWY'S

FD. "T" IRON 18" LONG
GUY POLE = ESE 80.51'
P.P. = NW 50.57'

NOTE: ROAD COMM. DUG FOR THIS COR. W/MOTOR GRADER-- NOTHING WAS FOUND.

RATIFIED BY PEER GROUP
IN ACCORDANCE WITH P.A. 345
ON Nov. 14, 1996
Wayne A. Mostrom CO. REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET 5/8"X24" BAR W/STD. COUNTY CAP IN MON. BOX
NE. HSE COR. (TOP FTDN.) = S54°W 112.58'
N&W IN SW. SIDE P.P. = N45°W 48.10'
N&W IN S. SIDE P.P. = N65°E 78.84'
N&W IN S. SIDE P.P. = S68°E 80.80'
COR. IS IN CL OF ROAD INTER.



LIBER **4** PAGE **271**

Signed by Wayne A. Mostrom
Surveyor's Michigan License No. 14100

Date 11/27/96

REMONUMENTATION