

NOV 15 1994

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

LIBER 4 PAGE 59

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

ST. JOSEPH (County) Located In: Corner Code: #1. Public Land Survey T 6S R 10W K-3

STATE OF MICHIGAN ST. JOSEPH COUNTY RECORDED

18 OCT 94 2:30 P.M.

CYNTHIA JARRATT REGISTER OF DEEDS

Register of Deeds Stamp & File Number

DAVID W. MOSTROM in a field survey on SEPTEMBER 8, 1994 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

Grid table with columns A-M and rows 2-13. A dot is marked at the intersection of column J and row 3.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(K-E) CORNER COMMON TO SECTIONS 1, 2, 11 & 12

NO EVIDENCE OF GLO WITNESSES 1888 BOOK B, PG. 368 ANCHOR NE 37.6' A.P. = S45°W 40.2 STOP SIGN = SE 42.36' 1885 (BOOK A, PG. 484) STONE BY FORMER SURVEYOR ROAD SIGN NW 36.50' STOP SIGN SE 44.50' STONE OVER STAKE 9" B. OAK = S44°W 0.50 8" W. OAK = N16 1/4°W 1.21 1974 SURVEY BY PS #14100 & LCRC IN BK 3, P. - 54 1987 SURVEY BY PS#32339 1992 SURVEY BY PS #14100

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner.

(K-3)

FOUND 1" X 33" IRON SHAFT IN MON. BOX (NOTHING UNDER IRON) POST = N40°W 46.50' A.P. = S45°W 40.29' 48" MAPLE = S40°W 64.9' 6" HICKORY = N50°W 61.35' 36" OAK = N50°E 86.2'

RATIFIED BY PEER GROUP IN ACCORDANCE WITH P.A. 345 ON OCT. 10, 1994 W.D. CO. REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(K-3) CORNER COMMON TO SECTIONS 1, 2, 11 & 12 SET 5/8" X 24" IRON BAR W/STD. CAP IN MON. BOX N & W IN E. SIDE OF 50" MAPLE = S40°W 40.25' N & W IN S. SIDE OF 6" HICKORY = N58°W 61.35' N & W IN W. SIDE OF 36" OAK = N60°E 86.20' N & W IN SW SIDE OF 10" POST = N40°W 46.50' N & W IN SW SIDE OF A.P. = S45°W 40.29'



Signed by [Signature]

Date OCTOBER 12, 1994

Surveyor's Michigan License No. 32339