

NOV 15 1994

004 PG 053

FILED

SEP 29 4 53 PM '94

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Cynthia R. Janott
REGISTER OF DEEDS
ST. JOSEPH CO MICH

For corners in

ST. JOSEPH

(County)

NOTTAWA TWP.

Located In:

Corner Code: K-4

- 1. Public Land Survey T 6 S R 10 W K-4
- T _____ R _____
- T _____ R _____
- T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
- in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
- Property in Sec. S _____ T _____ R _____

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, WAYNE A. MOSTROM, in a field survey on SEPTEMBER 8, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

K-4 1870'S SURVEY BY ANDREWS
SET STK & STONES MIDWAY
12" B.O. = S36½°W 64 1/3 LKS
4" W.O. = S53¼°E 41 LKS

1974 L.C.R.C. IN L-3, P-54 & 1974 SURVEY BY MOSTROM
SET IRON BAR MIDWAY BET. CORNERS
21" OAK = NW 38.85'
30" OAK = NW 47'
14" OAK = NE 22.39'
30" OAK = SE 27.65'
IN LINE W/FENCE TO W.
FENCE TO E. IS 8' N.

1992 SURVEY BY MOSTROM
FD. ½" BAR
IRON FD. = 33.0' EAST
30" OAK = N20°W 48'
24" OAK = N70°W 38.85'
16" OAK = N80°E 22.39'
34" OAK = S50°E 27'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-4
FD. ½" BAR ALONG SIDE 3/8" BAR
32" OAK = NW 38.85'
34" OAK = N21°W 48'
26" OAK = N81°E 22.39'
30" OAK = S54°E 27'
IRON BAR = E'LY 33.00'

RATIFIED BY PEER GROUP
IN ACCORDANCE WITH P.A. 345
ON Sept. 12, 1994
Wayne A. Mostrom CO. REPRESENTATIVE



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-4 (¼ COR. BETWEEN SEC'S 11 & 12)
SET 5/8" X 24" IRON BAR W/STD. CAP
N. & W 12" HIGH IN E. SIDE 32" OAK = N74°W 38.85'
N & W 36" HIGH IN NE SIDE 34" OAK = N21°W 47.00'
N & W 24" HIGH IN N. SIDE 26" OAK = N81°E 22.39'
N & W 12" HIGH IN N. SIDE 30" OAK = N54°E 27.0'
COR. IS IN C OF 4' ROAD CUT & IN FENCELINE TO WEST
FENCELINE TO EAST IS 8' NORTH

Signed by Wayne A. Mostrom

Date 9/15/94

Surveyor's Michigan License No. 14100