

NOV 15 1994

SEP 29 4 54 PM '94

COMMISSION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

Cynthia K. Janett  
REGISTER OF DEEDS  
ST. JOSEPH CO MICH

For corners in:

ST. JOSEPH (County)	Located In:	Corner Code #:
1. Public Land Survey	T <u>6S</u> R <u>10W</u>	<u>K-5</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, WAYNE A. MOSTROM, in a field survey on SEPT. 8, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

K-5

1892 SURVEY -BOOK A, PAGE 583

R.R.A.P. = N40°E 41.65'  
R.R.A.P. = N35°W 35.12'  
52" MAPLE = S70°E 75.10'  
14" OAK = S25°W 68.87'

1974 L.C.R.C. - L-3, P-54

"CORNER WAS RESET IN REMAINS OF ORIG. GOV'T POST"

MON. BOX 3" DEEP  
RAIL A.P. = NE 41.65'  
RAIL A.P. = NW 35.12'  
58" MAPLE = SE 75.10'  
14" OAK = SW 68.87'

ROAD COMMISSION - 1963

DROVE 3/4" PIPE THRU OLD WOOD STAKE, BRICK & TILE - SET MON. BOX

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-5

FD. 1" X 27" PIPE IN MON. BOX  
RAIL A.P. = N40°E 41.65'  
RAIL A.P. = N40°W 35.12'

RATIFIED BY PEER GROUP  
IN ACCORDANCE WITH P.A. 345  
ON 9/12, 1994  
W.A.M. CO. REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-5 (COR. COMMON TO SEC'S 11, 12, 13, 14)

SET 5/8" X 24" IRON BAR W/STD. CAP IN MON. BOX  
S. FACE RAIL A.P. = N40°E 41.65'  
S. FACE RAIL A.P. = N40°W 35.12'  
N. FACE RAIL A.P. = S46°E 36.25'  
N & W IN S. SIDE 8" HICK. = N50°W 55.75'  
CL RDWY (DIRT) TO N. = 3' EAST  
CL RDWY (DIRT) TO S. = 2' EAST  
CL E-W ASPHALT RDWY = NORTH 1'



Signed by Wayne A. Mostrom

Date 9/13/94

Surveyor's Michigan License No. 14100